PART 3: QUALITY ASSURANCE

CONTENTS

3.1	REF	ERENCED DOCUMENTS	3
	3.1.1	Source document	3
	3.1.2	Guidelines	3
3.2	INT	RODUCTION	4
3.3	PRO	DJECT QUALITY SYSTEM	4
	3.3.1	Key achievement criteria	6
	3.3.2	Design Report	6
	3.3.3	Contract Quality Plan	
	3.3.4	Engineer's Report	7
3.4	PRO	DJECT MANAGEMENT	9
3.5	MA	NAGEMENT OF PURCHASING	9
	3.5.1	Purchasing instructions.	
	3.5.2	Material supply	
	3.5.3	Subcontractor quality control	
3.6	COI	NTROL AND INSPECTION OF THE WORK	9
	3.6.1	Identifying and planning	
	3.6.2	Checking, inspection, testing and recording	10
3.7	NO	N-CONFORMANCE & QUALITY IMPROVEMENT	10
	3.7.1	Control of non-conforming work	
	3.7.2	Quality improvement	
3.8	SAF	ETY AND ENVIRONMENTAL MANAGEMENT	11
	3.8.1	Health and Safety	
	3.8.2	Environmental Management	
API	PENDIX 1	GUIDELINES AND FURTHER EXPLANATION	13
API	PENDIX I	I DESIGN REPORT	20
API	PENDIX I	II CONTRACT QUALITY PLAN	24
API	PENDIX I	V DESIGN CERTIFICATE	29
API	PENDIX V	DESIGN PEER REVIEW CERTIFICATE	30
API	PENDIX V	VI ENGINEER'S REVIEW CERTIFICATE	31
API	PENDIX V	VII ENGINEER'S COMPLETION CERTIFICATE	32
API	PENDIX V	VIII CONTRACTOR'S COMPLETION CERTIFICATE	33
API	PENDIX I	X NON-CONFORMANCE REPORT	34
AP	PENDIX 2	ENGINEER'S AUDIT & TEST SCHEDULE	35
API	PENDIX 2		40
	PENDIX 2		44
	PENDIX 2	-	45

Part 3: QUALITY ASSURANCE

APPENDIX	XIV	ENGINEER'S GRAVITY PIPE TEST CHECKSHEET	48	8
APPENDIX	XV	ENGINEER'S CONCRETE PRESSURE PIPE CHECKSHEET	TEST 50	0
APPENDIX	XVI	ENGINEER'S PRESSURE PIPE TEST CHECKSHEET	5	1
APPENDIX	XVII	CONSTRUCTION CHECKSHEET	52	2
APPENDIX	XVIII	CONSTRUCTION CHECKSHEET	53	3
APPENDIX	XVIV	CCTV REQUIREMENTS	54	4
APPENDIX	XVV	S224 ENGINEERING APPROVAL DATA CHECKLIST	5.	5
FIGURES				
Figure 1	Quality A	ssurance Flow Diagram		5
Figure 2	Responsib	pilities and Requirements Diagram		6

3.1 REFERENCED DOCUMENTS

Design

- NZS ISO 9000: 2006 Quality management systems Fundamentals and vocabulary
- Transit New Zealand Quality Standard TQS2: Second Edition, June 2005
- NZS 3910: 2003 Conditions of contract for building and civil engineering construction
- IPENZ Practice Note 02 Peer Review Reviewing the work of another engineer

www.ipenz.org.nz/ipenz/forms/pdfs/PN02 Peer Review.pdf

Construction

- Christchurch City Council Civil Engineering Construction Standard Specifications Parts 1-7 (CSS)
 - https://ccc.govt.nz/consents-and-licences/construction-requirements/construction-standard-specifications
- Guideline on the Briefing and Engagement for Consulting Engineering Services (2004) (ACENZ/IPENZ)

www.ipenz.org.nz

Where a conflict exists between any Standard and the specific requirements outlined in the Infrastructure Design Standard (COP), the COP takes preference (at the discretion of the Council).

The terms, and their definitions, used in this standard are consistent with those of NZS ISO 9000 and NZS 3910.

3.1.1 Source document

This Part of the Engineering Code of Practice (COP) is based on Part 3 of the *CCC Infrastructure Standard* (IDS), by agreement and with the consent of Christchurch City Council.

TQS2 was used a guide in the development of this section of the IDS. That standard was developed by Transit New Zealand as a framework for an acceptable quality management system for the suppliers of physical works on state highways, and came into effect as a mandatory requirement from July 1996.

The use of that standard by Christchurch City Council as a basis for Part 3 of the IDS has been with the kind permission of Transit New Zealand.

3.1.2 Guidelines

Notes have been included in <u>Appendix I</u> – Guidelines and Further Explanation. These are intended to aid in the understanding of this section, expand on the requirements and explain the application of a project quality system in more detail. Read them in tandem with the clauses in this section.

3.2 INTRODUCTION

Selwyn District Council aims to achieve well-designed and constructed assets for its ratepayers. Building and maintaining assets, regardless of whether they are created through the subdivision and development of land or the capital works process, is a partnership of developers, designers and contractors. Where quality principles are applied to both design and construction, real benefits result.

Selwyn District Council therefore requires the application of quality assurance for all physical works that result in assets being transferred to the Council. Any designer, contractor or supplier wishing to tender for capital works or any developer exercising a resource consent must implement this part.

Where the assets will be vested through subdivision, constructing assets in accordance with a Project Quality System will be a condition of subdivision consent. The developer must demonstrate compliance by providing and applying the project quality system, to substantiate the release of the subdivision compliance certificate, known as the 224(c) certificate. Similarly a contractor engaging in capital works is required to provide and apply a Contract Quality Plan during the contract period, which provides the supporting structure for the quality system. Refer to Appendix XVV for a schedule of the data to be provided for subdivision engineering approval for issue of a s224 (c) certificate.

This Part provides a framework for a quality management system. It has been developed by a Christchurch City Council internal working party and has been benchmarked against best national practice. The quality management system must ensure that all quality assurance issues relevant to a subdivisional land development or a capital works project are effectively defined, managed and communicated to ensure that all quality requirements are achieved.

3.3 PROJECT QUALITY SYSTEM

The project quality system must include documented procedures relating to all management, design and construction activities. This includes the following components:

- Project management, as described in clause 3.4;
- Management of purchasing, as described in clause 3.5;
- Control and inspection of the work, as described in clause 3.6;
- Non-conformance and quality improvement, as described in clause 3.7;
- Health and safety, as described in clause 3.8.1;
- Environmental management, as described in clause <u>3.8.2</u>.

The Project Quality System consists of a document trail comprising:

- the Design Report, as described in clause 3.3.2 and illustrated in the example in Appendix II;
- the Contract Quality Plan, as described in clause <u>3.3.3</u> and illustrated in the example in Appendix III;
- the Engineer's Report, as described in clause 3.3.4.
- These three documents support the certificate trail, which establishes compliance with the Project Quality System. The certificate trail includes:

- the Design Certificate (see Appendix IV) and Design Peer Review Certificate (see Appendix V), which complete the Design Report documentation;
- the Engineer's Review Certificate (see Appendix VI), which completes the Contract Quality Plan;
- the Engineer's Completion Certificate (see Appendix VII) and the Contractor's Completion Certificate (see Appendix VIII), which complete the Engineer's Report;
- the 224(c) Certificate or Practical Completion Certificate.

The issue of the 224(c) Certificate or Practical Completion Certificate is therefore dependent on the application of the Project Quality System and the provision of its related documentation. This interrelationship is set out in <u>Figure 1</u>.

Figure 1 Quality Assurance Flow Diagram

Resource Consent Application or Design Brief for Capital Works **Document Trail** Contract Engineer's Design Report Quality Report Plan 224(c) Certificate or Practical Engineer's and Design and Engineer's Completion Design Peer Contractor's Review of Certificate Completion Review Quality Plan Capital Works Certificates Certificates NZS 3910 Certificate Trail

Quality Assurance Flow Diagram

Quality assurance responsibilities and requirements are a combination of relationships across the investigation, design and construction phases. Figure 2 explains those relationships and the point at which they are applicable.




Figure 2 Responsibilities and Requirements Diagram

3.3.1 Key achievement criteria

Key achievement criteria are defined as elements of design or construction that are critical to the quality of the asset. These are typically found in the resource consent or project brief. They may also come out of particular aspects of the design e.g. the designer may require proof of levels on a weir at a particular place in the system to support compliance with a higher level key achievement criteria.

3.3.2 Design Report

Submit a Design Report, where required as a condition of consent in respect to a subdivisional land development or where specified in the project brief. Submit a Design Certificate to the Council along with the Design Report. Engineering acceptance is subject to presentation of this report.

The designer describes how s/he has:

- Identified and addressed the design, management, administrative and legislative requirements specific to the design;
- Planned the work to satisfy those requirements;
- Managed communication with stakeholders and other parties to the design;
- Reviewed/tested the design to ensure compliance with the quality requirements;

 Recorded design activities and maintained records and evidence of compliance.

If required as a condition of consent, peer review the design in accordance with *Peer Review – Reviewing the work of another engineer*. Submit a Design Peer Review Certificate to the Council along with the Design Report.

Where aspects of the design require expertise outside of the field of knowledge of the designer, provide a Design Certificate from a suitably qualified subconsultant designer to support the submission of the Design Report. Ensure additional information obtained from the sub-consultant designer regarding key achievement criteria or other matters is also incorporated in the Design Report.

3.3.3 Contract Quality Plan

Submit a Contract Quality Plan within the time frame and to the extent specified in the resource consent or contract. Submit an Engineer's Review Certificate to the Council along with the Contract Quality Plan. Where specified as a deliverable in the contract or as a requirement of resource consent, the Contract Quality Plan and Review Certificate must be subject to review and acceptance by the Council, along with any major amendments. Present the Contract Quality Plan and Review Certificate before physical works commence.

The contractor describes how s/he will:

- Identify and address the contract management (including traffic management, technical and environmental issues), administration and legislative requirements specific to the contract as detailed in clause 3.4 Project Management;
- Plan the work to satisfy those requirements;
- Control (manage) the work, including that undertaken by subcontractors, to comply with requirements;
- Manage communications with stakeholders and other parties to the contract;
- Inspect/test the materials and work to ensure compliance with the quality requirements;
- Address communication and reporting requirements;
- Manage, review and update management plans to ensure they remain relevant to the requirements of the contract and work being undertaken;
- Record contract activities and maintain records as evidence of compliance.
- Provide certification upon Practical Completion through submitting a Contractor's Completion Certificate.

Where aspects of the construction require expertise outside of the field of knowledge of the contractor, the contractor must provide a Completion Certificate from a suitably qualified subcontractor to support the submission of the Contractor's Completion Certificate. Ensure additional information obtained from the subcontractor regarding key achievement criteria or other matters is also incorporated in the Contract Quality Plan.

3.3.4 Engineer's Report

Submit the Engineer's Report upon completion of physical works, where required as a condition of consent in respect to a subdivisional land development

or where specified in the project brief.

The engineer describes how s/he has:

- Identified and addressed the quality management requirements specific to the project;
- Inspected, audited and tested the materials and work to ensure compliance with the quality requirements;
- Recorded project activities and maintained auditable records as evidence of compliance, including any non-conformance reports.
- Provide certification upon Practical Completion through submitting an Engineer's Completion Certificate. Present the completed audit records with the application for 224(c) certification. Refer to Appendix XVV for a schedule of the data to be provided for subdivision engineering approval for issue of a s224 (c) certificate.

Where aspects of the construction require expertise outside of the field of knowledge of the engineer, provide a Completion Certificate from a suitably qualified sub- consultant engineer to support the submission of the Engineer's Report.

3.4 PROJECT MANAGEMENT

Clearly state the responsibility, authority, necessary qualifications and relationships of the key personnel involved in achieving quality outputs. Include these in the Design Report or Contract Quality Plan.

In the case of capital works contracts for the Council include the responsibilities for safety and environmental management programmes, in accordance with relevant legislative requirements (as set out in clause 3.8 – Safety and Environmental Management).

3.5 MANAGEMENT OF PURCHASING

3.5.1 Purchasing instructions

Purchase orders that are significant in terms of achieving the project quality requirements must be in writing. They must contain a clear specification of the requirements.

3.5.2 Material supply

Check materials purchased for the project that are significant in terms of achieving the contract quality requirements. Confirm compliance with the specified requirements prior to incorporation in the project. Note the verification of compliance either on the relevant checksheet or some other appropriate record.

3.5.3 Subcontractor quality control

The contractor is responsible for the quality of materials supplied and work performed by its subcontractors. Include appropriate quality assurance procedures in the Contract Quality Plan, to control and monitor subcontractor compliance with the contract and/or Contract Quality Plan. Conduct planned periodic audits of subcontractor activity.

These procedures do not relinquish the responsibility of the main contractor. Ensure that the subcontractor is aware of specific technical and management requirements in the contract, and that these are incorporated in the Contract Quality Plan. Ensure that the subcontractor has appropriate controls in place for the management of any specific construction risks.

3.6 CONTROL AND INSPECTION OF THE WORK

Undertake the work in a planned and controlled manner to ensure that the quality requirements are realised. Demonstrate that the following has been undertaken on all projects:

- Identify the key achievement criteria;
- Plan how these will be realised;
- Control the work in conformance with the project quality system;
- Check, inspect or test the work and verify that it conforms to the specified requirements;
- Record the results as documentary evidence of compliance.

This clause relates to both design and construction works and requires that all the processes involved are properly managed.

3.6.1 Identifying and planning

Systematically identify from the consent the key achievement criteria of the project for each discipline. Identify the key achievement criteria at each stage to satisfy all the requirements of clause 3.6.2 – Checking, inspection, testing and recording. Use these as a basis for developing the Design Report, Contract Quality Plan or Engineer's Report. Include documentation of constraints, assumptions and base data, e.g. site investigations, in these documents.

Apply documented procedures to the extent necessary to ensure that those performing the work fully understand what is required, or where their absence could create a risk to the quality or safety of the work being undertaken.

3.6.2 Checking, inspection, testing and recording

Check, inspect or test against all the identified key achievement criteria to verify compliance during design and construction and on final completion. Specify the methods, specification references, frequency, timing, responsibilities and necessary qualifications for checking, inspection and testing in the Design Report, Contract Quality Plan and Engineer's Report. Measure compliance against quantified acceptance criteria based on the COP and/or specification requirements and Appendix 4 of the *Guideline on the Briefing and Engagement for consulting Engineering Services* (2004) (ACENZ/IPENZ) which can be viewed on the IPENZ website (www.ipenz.org.nz). Document the results and retain as part of the quality records.

Clearly indicate any "hold' or "witness points" in the Design Report, Contract Quality Plan or Engineer's Report, where the project requires checking, an inspection and/or approval to proceed (i.e. internally and/or from the Council). Establish systems to record the findings, any remedial action initiated and the final approval to proceed. Treat non-conforming work in accordance with clause 3.7-Non-Conformance and Quality Improvement.

Where there is a requirement to use third party accredited agencies, include the details of compliance methods in the Design Report, Contract Quality Plan or Engineer's Report.

3.7 NON-CONFORMANCE & QUALITY IMPROVEMENT

3.7.1 Control of non-conforming work

The designer must have a procedure to ensure that design work that does not conform to the specified requirements is either:

- redesigned to meet the specified requirements; or
- accepted by concession from the Council.

Record all non-conforming work on the relevant design record and/or the relevant design checksheet.

The contractor/engineer must have a procedure to ensure that construction work that does not conform to the specified requirements is either:

reworked to meet the specified requirements;

- accepted with or without repair by concession from the Council;
- regraded for alternative use;
- rejected and replaced.

Record all non-conforming work on the relevant construction checksheet.

If the construction non-conformance is significant in that it either:

- results in the need for written concession;
- results in delay or interference to the work or to other parties;
- indicates that the fault has occurred due to the use of incorrect work practices and/or failure of materials and could have been prevented;
- occurs sufficiently frequently as to indicate a problem in training or procedures,
- produce a Non-Conformance Report (NCR) and send to the Council.

The report and supporting documentation must clearly indicate the action to be taken to rectify the fault, the timeframe and responsibilities. It must be authorised by the designer or engineer. An example of a report is enclosed in Appendix IX – Non-Conformance Report.

In cases involving concessions, the designer or engineer and the Council must approve the proposed rectification (the corrective action) of the non-conforming work in writing and prior to implementation.

3.7.2 Quality improvement

Investigate the cause (as opposed to the symptom) of reported non-conforming work. Record proposals for improving the company's quality system on the Non-Conformance Report, to prevent the recurrence of a specific non-conformance. Send all corrective action proposals to the Council.

Ensure that the proposed corrective action is properly and effectively implemented.

3.8 SAFETY AND ENVIRONMENTAL MANAGEMENT

3.8.1 Health and Safety

A health and safety programme is mandatory for all contract quality plans submitted as part of a capital works project. It is not a Council requirement of subdivision consents.

Operate a formal health and safety programme, which complies with the statutory requirements of the Health and Safety in Employment Act and any subsequent revisions and associated regulations. To the extent practical and permissible by law, health and safety policies and procedures should be integrated into the engineer's and contractor's quality system.

3.8.2 Environmental Management

Operate a formal environmental management programme that complies with the statutory requirements of the Resource Management Act, any associated Regulations and any other specific requirements set out in any applicable

resource consent. To the extent practical and permissible by law, integrate the programme into the quality system.

The Contract Quality Plan must identify all compliance issues relating to the Resource Management Act, including any conditions contained within the project related resource consents.

APPENDIX 1 GUIDELINES AND FURTHER EXPLANATION

PROJECT QUALITY SYSTEM (clause 3.3)

The project quality system identifies how the requirements of the project were or will be addressed. These may include quality, safety, environmental, technical and general management requirements. This may be achieved by:

- adopting industry best practices;
- adopting or adapting documents developed for the same or similar activity on previous jobs;
- preparing new documents for those activities which are new or substantially different from anything undertaken previously.

Provide details of how all the identified requirements were or will be planned, controlled (managed), checked or inspected for compliance and the results recorded. Include provision for document control, including review and approval of the quality systems. The identified requirements will include the key achievement criteria but also those routine items which, through being achieved, will provide a quality asset.

For example, if a consent had a condition like "The surface water management system shall rely on stormwater disposal to ground in accordance with the consent conditions of CRCXXXX.1", the key requirement (achievement criteria) to ensure this condition was met would be to demonstrate that the design soakage rates for any infiltration system can be achieved on-site.

Each part of the COP contains examples, for guidance, of records that can be provided to support the project quality system e.g. thrust block design calculations in clause 7.3.2 – Design records (Water Supply).

DESIGN REPORT (CLAUSE 3.3.2)

A Design Report is a document specific to a design, which describes how the design was managed and administered in compliance with the requirements of the COP and the resource consent or project brief.

Include a list of project personnel, their qualifications and their contact details. List the procedures and design checksheets that were used to effectively manage the design. These procedures should include the necessary qualifications of key personnel as they relate to particular tasks. Highlight exceptional aspects of the project that must be covered by the Contract Quality Plan.

For the example given above, information provided through the project quality system to support the assertion of compliance (which is more substantial as the condition is a key achievement criteria) might include, in the Design Report:

- Methodology to determine the design soakage rate.
- Design checksheet (see guidelines to clause 3.6.2) including the assumptions upon which the design is based (see clause 5.4.3 Design records (Stormwater) bullets) and their source.
- Calculations leading to the design infiltration.
- Record of key achievement criteria for inclusion in the CQP.

- Design Certificate.
- Designers qualifications relevant to infiltration design.
- Design Peer Review Certificate if required.
- Specific requirements for OMM to preserve ongoing compliance.
- Supporting information retained in the project quality system might include:
- Alternatives explored.
- Contractual requirements around the key achievement criteria into the CQP.
- Quick check of the design infiltration, by an alternative method if possible.

An example of a simple proforma Design Report setting out the minimum requirements of the COP is provided in Appendix II. It is an example only and designers may develop their own format to suit their specific needs.

CONTRACT QUALITY PLAN (CLAUSE 3.3.3)

A Contract Quality Plan is a document specific to the project, which describes how the contract works will be managed and administered in compliance with its requirements.

Include, or otherwise reference, the procedures and the checksheets necessary to effectively manage the contract works. These procedures should include the qualifications of key personnel as they relate to key tasks particularly the key achievement criteria e.g. the connection to the Council water reticulation must be undertaken by an authorised water installer. The following is a guideline of the information that should be included in the Contract Quality Plan:

- A statement of policy with respect to the timing and frequency of internal reviews and/or audits of the quality plan during the project.
- A schedule of the contractual quality records to be kept.
- A list of subcontractors.
- Procedures for auditing subcontractor compliance to the quality plan.
- A schedule of inspection and/or testing of materials and/or completed works, clearly indicating 'hold' or 'witness' points.
- Documented procedures included, or referenced, for all activities.
- Non-conformance & quality improvement procedures included, or referenced.
- Provisions for traffic management and environmental management plans included or referenced.

For the example given above, information provided through the project quality system to support the assertion of compliance (which is more substantial as the condition is a key achievement criteria) might include, in the Contract Quality Plan:

(Pre-construction)

- Engineers Review certificate.
- Inspection and test schedule highlighting the infiltration test requirement.
- (Post-construction)
- Contractor's Completion Certificate.

- Inspection and test schedule proving compliance is achieved.
- Supporting information retained in the project quality system might include:
- Infiltration test record sheets.

An example of a simple proforma Contract Quality Plan is provided in Appendix III. This sets out the minimum requirements the Contract Quality Plan must achieve for this standard. It is an example only and contractors may develop their own format to suit their specific needs.

Prepare site-specific Erosion and Sediment Control Plans (ESCP) in accordance with clause 4.8 – Erosion, Sediment and Dust Control (Geotechnical Requirements).

As noted above, processes and procedures for the management of subcontractors must be stipulated in the Contract Quality Plan. This is especially important where subcontractors perform a large component of the works (e.g. earthworks).

ENGINEERS REPORT (CLAUSE 3.3.4)

An Engineer's Report is a document specific to a project, which describes how the project was managed and administered in compliance with the COP, the *Construction Standard Specifications*, the Contract Quality Plan and the resource consent or project brief. It provides background information to the release of the 224(c) certificate.

The following is a guideline of the information that should be included in the Engineer's Report:

- A schedule of the project and contractual quality records that have been kept.
 A summary of the quality records proving compliance is to be submitted to the Council.
- What procedures were employed for auditing contractor and subcontractor compliance with the quality plans.
- For the example given above, information provided through the project quality system to support the assertion of compliance (which is more substantial as the condition is a key achievement criteria) might include, in the Engineers Report:
- Engineers Completion Certificate.
- Non-conformance Reports if generated.
- OMM as it relates to the ongoing achievement of this condition.
- Audit and test schedule proving compliance has been achieved.

PROJECT MANAGEMENT (CLAUSE 3.4)

The project management structure need only show the key positions or functions. In many companies an individual can hold more than one position or be responsible for more than one function. The designer and the engineer can be the same person or organisation.

Relate job descriptions to positions and named individuals. They can be quite simple and should only state the principal responsibilities of the position, any necessary qualifications and the reporting lines. Examples of a management structure and job descriptions for a typical subdivision and a small/medium contractor are enclosed in Appendix II – Design Report section 1 and Appendix III – Contract Quality Plan section 3.

PURCHASING INSTRUCTIONS (CLAUSE 3.5.1)

Ensure that purchasing instructions are precise; otherwise there is a significant risk of not getting what is needed. Include, as appropriate:

- the product type, class, and size etc;
- the quality standards;
- the quantities;
- the scope of the work;
- the delivery details;
- the completion dates.

It may not be necessary to fully describe the requirements in every case e.g. when there is a record that the supplier has previously supplied full details or a copy of the specification and that the detail is current. In this instance, it would be sufficient to order by reference to those previously supplied details.

MATERIAL SUPPLY (CLAUSE 3.5.2)

Checking for compliance should preferably be done on receipt of the materials. The "verification" referred to can be recorded when completing the relevant checksheet (refer to the examples given in Appendices XIII - XVII). Attach any supporting documentation to the checksheet, such as delivery dockets or supplier certificates of compliance, which provide evidence of the type, grade, and class etc of material used.

Keep records of material tests that are traceable to defined sections of the work e.g. seven and 28 day concrete crushing strength test results, basecourse sand equivalent tests ex-supplier.

IDENTIFYING AND PLANNING (CLAUSE 3.6.1)

Each project is unique in that it:

- has technical requirements which may vary in part or full from other projects;
- will have a different scope of work from other projects, which is also likely to alter during the course of the project;
- will be in a different location and therefore will have different external influences from other projects;
- will utilise different resources;
- will have its own programme etc.

The identification of the project requirements is therefore important and must be undertaken in some systematic and documented manner. The project must be planned and managed to suit its unique set of characteristics, either by "highlighting" the key achievement requirements in the relevant sections of the consent, project brief or contract specification, or in a more formalised manner, by listing the requirements on a form. These key requirements must also be communicated between the various parties to the project.

The procedures should follow a standard format and be "user friendly". They will describe how individual work activities are planned, controlled and inspected for compliance with the specification requirements. They will:

- describe how the activity or task will be performed;
- define key task responsibilities and required qualifications;

- describe how key design parameters which directly impact on the effectiveness of the design are communicated;
- indicate the sequence;
- specify the resources to be used;
- be written in precise and easily understandable language.

They should contain as a minimum the information outlined in the example in Appendix XII – Quality System Work Procedure.

Examples of work activities that would be covered by procedures include: surface and groundwater modelling; survey and setout; placement of unbound granular basecourse; stormwater pipework; traffic control. For work activities that are more or less standard, procedures from previous projects may be adopted or adapted.

CHECKING, INSPECTION, TESTING AND RECORDING (CLAUSE 3.6.2)

The documentation requirements associated with checking, inspection, testing and recording need not be complex. The checksheets are useful in that they provide a breakdown of the checks that should be performed and, when completed, serve as a record. They should be developed for each key design and work activity and should contain the quality requirements as reminders.

The design checksheet should:

- include the constraints, assumptions and base data;
- identify the personnel responsible for the design;
- record that the design has been checked and the method used;
- provide for "signing-off" at the bottom of the sheet after a fully complying "design check".

The engineer's checksheet should:

- identify the personnel responsible;
- provide for "signing-off" at the bottom of the sheet.
- Examples of engineer's checksheets are included in Appendices XIII XVI.

The construction checksheet should:

- provide a checklist of the items to be inspected;
- include the acceptance criteria;
- identify the personnel responsible for doing the inspection;
- contain space for recording that compliance of the individual items has been attained;
- contain reference to further records generated by non-conformances;
- provide for "signing-off" at the bottom of the sheet after a fully complying "final inspection".
- Examples of construction checksheets are included in Appendix XVII and XVIII.

An audit or inspection and test schedule should provide a full listing of all audits, inspections and tests of materials and completed works. It should clearly indicate 'hold' or 'witness'

points and include signing off by the contractor, the engineer and the Council where required. A sample engineer's audit and test schedule is contained in Appendix X and a sample inspection and test schedule is contained in Appendix XI.

CONTROL OF NON-CONFORMING WORK (CLAUSE 3.7.1)

It is inevitable that, even with excellent practices and controls, some degree of defective workmanship or material will occur. When it does, it is important that it is properly handled to ensure that the defects are rectified in the appropriate way.

A non-conformance should be considered an opportunity for improvement, rather than to apportion blame. By adopting this philosophy, identifying a non-conformance provides an opportunity to learn from the mistake and (more importantly) prevent it happening again.

Note that there is a clear differentiation between what should be considered a "routine construction issue" or a "routine design step" and a non-conformance. Ensure this is understood by and communicated to all staff. A construction issue, such as soft subsoils, is often identified (and reasonably expected) during a project and does not therefore necessitate the raising of a Non-Conformance Report, unless procedures have not been followed. The inability to achieve the minimum grade on a sewer design is a non-conformance and must be reported, as is the inability to achieve a passing Benkelman Beam test or infiltration test.

A non-conformance exists, and therefore a report should be raised, in all instances where a defect in the work or design occurs that indicates that the required standard or key achievement criteria prescribed in the Design Report, Contract Quality Plan or Engineer's Report has not been met, e.g. failure to achieve compaction results, pre-seal inspection etc. For this process to be successful it must be handled in a positive and constructive manner, without unnecessary recrimination.

Any non-conforming work that is subject to follow-on work by other parties must be clearly denoted as such to alert the other parties to its non-conforming status.

QUALITY IMPROVEMENT (CLAUSE 3.7.2)

The objective is to reduce, if not eliminate, the root causes of the recurring inefficiencies and errors which have caused or can cause non-conforming work, i.e. to find a permanent cure for the problem, not just a "quick-fix". This provides a formal and disciplined procedure for identifying, investigating and correcting inefficiencies and shortcomings in a company's work practices.

There can be significant benefits to the company from the positive application of quality improvement, through reducing the incidence of non-conforming work and improving efficiency, to reducing costs including those of rework. Common causes of non-conforming work that can be addressed are:

- lack of training.
- lack of resources.
- poor communication / incomplete instructions.
- inadequately defined work practices.
- inadequate supervision.

ENVIRONMENTAL MANAGEMENT (CLAUSE 3.8.2)

Environmental management is an integral part of project management and therefore will be most efficiently operated within the framework of the project's quality system.

Design the environmental management programme in full compliance with the Resource Management Act. Specific activities that may require resource management consents include:

- management of stockpile material.
- management of disposal areas.
- the use of chemical sprays and fertiliser.
- noise and dust nuisance.
- prevention of fuel and oil spills including the actions taken if an oil spill occurs.
- control of silt, contaminants and stormwater runoff.
- the alteration of, or taking water from, waterways.
- work around protected trees.
- redirection of groundwater.

This is by no means an exhaustive list. Consider (if not contractually required to) developing a formal Environmental Effects Register. Also identify these matters in an assessment of environmental effects, for applications for subdivision consent.

APPENI	DIX II DESIGN REPORT	
(contract	name/subdivision name)	
(contract	/subdivision consent number)	
Copy No	e: of	
Version:		
Date of I	ssue:	
Date of I		
CONTE	NTS:	
1	Project Personnel and Design Management	21
2 3	Sub-consultant designers Full Description of Work	21 22
4	Quality Control and Inspection	22
5	Environmental Management	23
6	Concessions	23
7	Design Check and Review	23
8	Design Records	23
O	Design Records	23
APPENI	DICES: (attach these – as applicable)	
1 ₋ I	Design Certificate <see appendix="" example="" in="" iv=""></see>	
	Design Peer Review Certificate < see example in Appendix 1 V	
	Non-Conformance Report <see appen<="" example="" in="" td=""><td></td></see>	
DESIGN	N REPORT APPROVALS:	
This Des	ign Report has been:	
	Prepared by:	
	(Designer)	(Name/Sign/Date)
	Approved by:	
	(Principal designer)	(Name/Sign/Date)
	Reviewed by:	
	(Peer Reviewer)	(Name/Sign/Date)

1 Project Personnel and Design Management

Activity	Name of Sub-consu	ltant designer
	ndertook the following design activities	:
This list should include dea 2 Sub-consultant desi	ails of different design specialists, interi	nal reviewers and aud
		,
		<u> </u>
Name	Position Title	Responsibility
	el have been involved in this design:	
Contact Ph (Mobile): Telephone:		:
A 11	ndertaken):	
Telephone:	гах:	
Contact Ph (Mobile):	Contact Ph (A/H)	· · · · · · · · · · · · · · · · · · ·
Address:		
Sub-consultant designer:		
Telephone:		
Contact Ph (Mobile):	Contact Ph (A/H)	:
Name:Address:		
Developer:		
Telephone:	Fax:	

Sub-consultant designers were selected in accordance with company policies and procedures, and were provided with copies of the relevant project briefs and/or resource consents requirements and/or drawings prior to commencement of the work.

Sub-consultant designers were subject to monitoring and their work was subject to periodic internal audit.

3 Full Description of Work

This section contains a full description of the work included in the Design Report. It should include a description of:

- the existing pre-development site including surrounding development and existing landscaping or reserve areas;
- the proposed overall development stating the level of activity such as number of households, number and type of businesses, or facilities that will be serviced and the extent of the assets to be constructed such as landscaping, lighting, reserve structures;
- assessment of ground conditions noting the affect on material and installation requirements of landscaping assets being constructed;
- all key design and quality requirements for all assets as required by the Council
 and Developer such as minimum levels of service to be met as stated in Council
 activity management plans or standards, materials to be used with reference to
 relevant standards;
- assessment of how the design provides for replacement of components to be used and the requirement to meet durability targets with consideration of life cycle costs;
- Evidence of consultation, if applicable;
- the constraints, parameters, assumptions and raw data on which the design for the assets is based with design flow assumptions and standards covering storm water, sewer, water supply and transportation;
- data manipulation methods used e.g. computer software, methodologies.

4 Quality Control and Inspection

Procedures and design checksheets were used to control the design and verify compliance with the quality requirements. The following documents were used for this design:

Identifier	Title			
The documents can be made availab	le for the Council's review, if requested.			
Exceptional aspects of this project to	be covered by the Contract Quality Plan include:			

5 Environmental Management

The following Resource Consents, relevant to the design, have been obtained:

In accordance with the resource consent/s, environmental controls relating to this particular design will be outlined in the Contract Quality Plan.

6 Concessions

If, during the process of design, work is identified which does not conform to the specified requirements and will require a concession from the Council, submit a Non-conformance Report as part of the Design Report. The concession proposed will be discussed and must be approved by the Council prior to execution.

7 Design Check and Review

Undertake internal design reviews, to verify the design outlined and/or referenced in this Design Report, in accordance with "Reviewing the work of another engineer". Include written documentation of this review, by checksheet, calculations carried out by hand or another method to check design calculations, or document here.

Undertake a peer review, to verify the compliance and effectiveness of the design, in accordance with "Reviewing the work of another engineer". Document the review here or include as an Appendix.

This review shall be specific only to those aspects of the works in which the reviewer is competent i.e. more than one reviewer may be required where the development incorporates specialised disciplines.

Record, report and action the review findings.

8 Design Records

0 0	ere produced for this design and are appended cifications, calculations, material specification					
elsewhere, photos etc.)						
The following completed checksheets are appended.						
The following completed checksheets are appended.						
The following completed check Checksheet No.	sheets are appended. Title					
	Title					
Checksheet No.	Title					
Checksheet No.	Title					

APPENDIX III **CONTRACT QUALITY PLAN** (contract name/subdivision name) (contract/subdivision consent number) Copy No: _____ of ____ Version: Date of Issue: **CONTENTS:** Contract Personnel 25 2 Document Control 25 3 Contract Management 26 4 Subcontractors 26 5 Quality Control and Inspection 27 **Environmental Control** 28 7 Non-Conformance 28 Contract Records 8 28 **APPENDICES:** (attach these – as applicable) 1 – Construction Programme 2 – Inspection & Test Schedule < see example in Appendix XI> 3 – Site Safety Plan 4 – Traffic Management Plan(s) 5 – Erosion and Sediment Control Plan 6 - Non-Conformance Report - < see example in Appendix IX> 7 – Contractor's Completion Certificate < see example in Appendix VIII> **CONTRACT QUALITY PLAN APPROVALS:** This Contract Quality Plan has been: Prepared by: (Name/Sign/Date) Approved by: (Name/Sign/Date) (Engineer) Approved by:

(Contractor)

(Name/Sign/Date)

1 Contract Personnel

Contractor: Name:				
A ddmaga.				
T 1 1	bile):	Contact Ph (A/H) Fax:):	
A 11				
	bile):	Contact Ph (A/H) Fax:		
A ddmaga.				
	bile):	Contact Ph (A/H) Fax:):	
A d due e e .				
·	bile):):	
2 Document This Contract Q		a controlled distribution as	follows:	
Copy No	Issued To		Date	Version No
1	<contract manager<="" td=""><td>></td><td></td><td></td></contract>	>		
2	<site supervisor=""></site>			
3	<all subcontractors<="" td=""><td>3></td><td></td><td></td></all>	3>		
4	<other></other>			
5	<engineer (for="" review<="" td=""><td>w and acceptance)></td><td></td><td></td></engineer>	w and acceptance)>		
6	Council (for review of	and acceptance)		

This CQP will be subject to periodic review during the course of the contract. All holders of controlled copies listed above will be issued with updates to this document as and when they occur.

3 Contract Management

The following key	personnel have	been assigned to	this contract:

	Name	Title
	<pre><or insert="" organisation<="" pre="" your=""></or></pre>	chart here>
	Key responsibilities and author	orities are as follows:
a)	Overall responsibility for the m developer and the engineer:(Title)	anagement of the contract and principal contact with the
b)		olve issues of dispute relating to compliance with the ontract and this quality plan and rectification of non-
c)	supervision, control and inspect the developer or engineer. Au	d to the required level for the day to day on-site tion of the works and communicate on such matters with athorised to receive, on behalf of the contractor, any or engineer (refer NZS 3910 Clause 5.2.1):
d)	Responsible for on-site Traffic (Title)	Control activities, qualified to STMS level:
e)	Responsible for compliance wi (Environmental Management):(Title)	ith the requirements of the Resource Management Act
f)	Preparation and amendment of ((Title)	this quality plan:
g)	Approval of this quality plan:(Title)	
4 Sub	contractors	
Subcontr	actors will undertake the following	ng work activities:
A	Activity	Name of Subcontractor

All Subcontractors are required to operate in accordance with this Contract Quality Plan.

5 Quality Control and Inspection

Procedures, construction checksheets and inspection and test schedules will be used to control the work and verify compliance with the quality requirements. The following procedures will be adopted for this contract or will be prepared in advance and be made available on site:

Identifier	Title

These can be made available for the Council's review, if requested.

Compliance checksheets are appended to the various parts of the CSS, which may provide initial guidance on what to consider when compiling construction checksheets.

An example of an inspection and test schedule is contained in Appendix XI. The schedule should indicate the frequency, timing, type of both inspection and/or tests required to be performed on the materials and at certain stages of construction. This schedule would be signed off as the specified activities are completed, and once completed would then serve as a Contract Record (refer clause 3.5.2 – Material supply).

In addition to the inspection and test schedule, the following key 'Hold' and 'Witness' points have been identified by the engineer as requiring inspection and approval by the engineer and/or the Council prior to further construction. They will be documented on the relevant construction checksheet.

Key achievement criteria may suggest some of these points. 'Hold' or 'witness' points could include:

- Site establishment;
- Commencement of works;
- Formwork or foundations prior to pouring concrete;
- Prepared earthworks and subsoil drainage prior to filling;
- Completed earthworks and prepared subgrade prior to topsoil or metalcourses;
- Confirmation of thrust block ground conditions and design;
- Complying polyethylene pipe weld preconstruction joint tests;
- Drainage and water reticulation bends, junctions and inspection points prior to backfilling, to allow as-builting;
- Utility reticulation prior to backfilling;
- Water and drainage reticulation during testing;
- Sterilisation of watermain;
- Finished subbase before the placement of basecourse;
- Finished basecourse before the commencement of surfacing or paving;
- Finished surface prior to roadmarking;

- Landscape areas formed and plants on site prior to planting;
- Construction safety audit;
- CCTV inspections;
- Practical Completion inspection;
- Defects Liability inspection for planting;
- Defects Liability inspection for roading etc;
- Defects Liability for stormwater.

6 Environmental Control

The following Resource Consents, relevant to the works undertaken and/or materials used in this contract, have been received:

These have been reviewed and appropriate controls have been put in place to manage and/or mitigate the risk.

In accordance with contract requirements, *<if applicable>* environmental controls relating to this particular contract and/or the work being undertaken are outlined *<delete as applicable>* further in the attached documentation/in the site-specific Erosion and Sediment Control Plan appended. The compliance and effectiveness of management controls will be subject to periodic review.

7 Non-Conformance

If, during the process of inspection, work is identified which does not conform to the specified site requirements, a Non-Conformance Report will be prepared by the person at 3 b). The rectification proposed will be discussed and agreed with the engineer and will be stated on the NCR.

A proforma Non-Conformance Report is attached, Appendix IX.

8 Contract Records

The following records will be produced for this contract:

(e.g. site meeting minutes, construction checksheets, photos, inspection and test schedules, test results, construction programmes, completion documentation, as-built records)

Refer to Appendix XVV for a schedule of the data to be provided for subdivision engineering approval for issue of a s224 certificate. The data required may be varied depending on the size of the subdivision or the assets that will be vested.

APPENDIX IV

DESIGN CERTIFICATE

INFRASTRUCTURE/ LAND DEVELOPMENT

ISSUED BY:
(Design firm or suitably qualified design professional)
TO
(Owner/Developer)
TO BE SUPPLIED TO:
(Territorial authority)
IN RESPECT OF:
(Description of infrastructure/land development)
AT:
(Address)
to the control of the
has been engaged by(Design firm or suitably qualified design professional) (Owner/Developer)
to provideservices in respect of the infrastructure/land development described above. I have the qualifications and experience relevant to this project as set out herein and have designed the subject works.
I on behalf of
(Designer) (Design firm)
confirm that the design is to current good engineering practice, and that it satisfies all relevant resource consent conditions.
The design firm issuing this statement holds a current policy of professional indemnity insurance of no less than \$
(Minimum amount of insurance shall be commensurate with the current amounts recommended by IPENZ, ACENZ, TNZ, INGENIUM.)
Qualifications and experience:
(Signature of designer)
Copyright waived

APPENDIX V DESIGN PEER REVIEW CERTIFICATE

INFRASTRUCTURE/ LAND DEVELOPMENT (Design peer review firm or suitably qualified design peer review professional) (Owner/Developer) TO BE SUPPLIED TO: (Territorial authority) IN RESPECT OF: (Description of infrastructure/land development) DESIGNED BY: (Design firm/Designer) ____ has been engaged by _____ (Design peer review firm or suitably qualified design peer review professional) (Owner/Developer) to provide design review services in respect of aspects of the above work, which is described in the specification and shown on the drawings numbered _____approved by _____(Territorial authority) under consent number _____on ____ As an independent professional, I have reviewed the design assumptions, methods, accuracy and conclusions. I have sighted the conditions of consent to the works and the approved specifications and drawings. In my professional opinion and based upon reasonable enquiry, this review, information supplied by the designer and the designer's certification (copy attached), I _____ confirm on behalf of _____ (Design Firm) the acceptability of the design and that the design complies with the above consent and current good engineering practice, subject to the findings below if any. (Signature of Design peer reviewer) NZIS ACENZ **IPENZ** (Professional qualifications)

Findings:

(Address)

APPENDIX VI ENGINEER'S REVIEW CERTIFICATE

REVIEW	OF	CONTRA	ACT O	UAL	ITY	PLA	١N
--------	----	--------	-------	-----	-----	-----	----

ISSUED BY:							
	(Engineering consultancy fi						
TO:	(Owner/Developer)						
TO BE SUPP	LIED TO:(Territorial authority)						
IN RESPECT	OF:(Description of infrastructu						
DESIGNED E	BY:(Design Firm/Designer)						
AT:	(Address)						
ĭ	on	hehalf of					
(Engineer)		ring consult			••••••	•	
have reviewed	d the Contract Quality Plan	(a copy of	which is	attached)			
I confirm the Assurance:	e following have been pr	rovided in	accord	ance with	COP P	art 3: Ç	Q uality
QualityContractSubcontractProcedutSite SaftNon-contract	et personnel and contact deta policy statement enclosed et management and responsi stractors listed ures are documented and ho fety and Environmental con- enformance process detailed et records listed	ibilities set old or witne trols detail	ess point	s listed			
			.Date:				
	ature of engineer) Mei	mber	NZIS	ACENZ	IPENZ		
(Professional q	qualifications)						
• • • • • • • • • • • • • • • • • • • •	(Address)	• • • • • • • • • • • • • • • • • • • •	•				

APPENDIX VII ENGINEER'S COMPLETION CERTIFICATE

INFRASTRUCTURE/ LAND DEVELOPMENT

ISSUED BY:	(Engineering consultan				
TO:					
	(Owner/Developer)		•••••	•••••	••••••
TO BE SUPPLI	IED TO:(Territorial authority)				····
IN RESPECT C	OF:(Description of infrastr			······································	
AT:					
		(Address)			
(Engineering con	nsultancy firm or suitably	y qualified engineer)	(Owner	/Developer)	
	and development descr				ction of the
	ered				
	 ate)		•••••	(1errii	orial authority
I	confirn	n on behalf of			
listed below if	aged the subject work any, have been con at they satisfy all relev	s and that the works	s, other than nce with cu	irrent good	nding works
indemnity insur	g consultancy firm iss rance of no less than \$				•
	ount of insurance by IPENZ, ACENZ, T			the curre	nt amounts
	gnature of engineer)	Date	:		
	rofessional qualification		NZIS	ACENZ	IPENZ
	ddress)				
Outstanding wo	orks				
••••		• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •	•••••	•••••

APPENDIX VIII CONTRACTOR'S COMPLETION CERTIFICATE

INFRASTRUCTURE/ LAND DEVELOPMENT ISSUED BY: (Contractor) TO: (Owner/Developer) TO BE SUPPLIED TO: (Territorial authority) IN RESPECT OF: (Description of infrastructure/land development) AT:..... (Address) has been contracted by Owner/Developer) to carry out and complete certain infrastructure/land development in accordance with ("the contract"). I,a duly authorised representative of (Duly authorised representative) (Contractor) (Contractor) the works, other than those outstanding works listed below if any, in accordance with the relevant resource consent conditions. Date: (Signature of authorised representative) (Contractor) (Address) Outstanding works

Copyright waived

(provide precise location, detailed description and sketches as appropriate) Company responsible for NC Contractor (sign/date) 2. PROPOSED CORRECTIVE ACTION (provide details with sketches)	Con	tract Name/No:	NCR Ref No:
2. PROPOSED CORRECTIVE ACTION (provide details with sketches) 3. APPROVALS: 3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)	1.		
2. PROPOSED CORRECTIVE ACTION (provide details with sketches) 3. APPROVALS: 3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)		Company responsible	for NC
3. APPROVALS: 3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)		Contractor (sign	/date)
3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)	2.		
3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)			
3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)			
3.1 The corrective action is accepted/ not accepted/ accepted subject to atta conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)			
conditions. Engineer (sign/date) Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)			
Council (sign/date) 3.2 The corrective action has been completed. Certified: (sign/date)	3.	APPROVALS:	
3.2 The corrective action has been completed. Certified: (sign/date)	3.	3.1 The corrective a	ction is accepted/ not accepted/ accepted subject to attache
Certified: (sign/date)	3.	3.1 The corrective a conditions.	
	3.	3.1 The corrective a conditions. Engineer	(sign/date)
Reviewed: (sign/date)	3.	3.1 The corrective a conditions. Engineer Council	(sign/date) (sign/date)
Approved: (sign/date)	3.	3.1 The corrective acconditions.Engineer Council3.2 The corrective according to the corr	(sign/date) (sign/date) tion has been completed.

APPENDIX X ENGINEER'S AUDIT & TEST SCHEDULE

Testing			Inspection Verifica		Verification	tion			
Phase	Test / Material Certificate Audit Frequency	Specification Reference		Engineer Y/N	Hold Point Y/N	Acceptance Cri	teria	Signed / Accepted / Dat	
	ow information is an or infrastructure and				e audit and test	plans unique	to the projec	t, incorporating	that project's
TNZ M/4:AP20	All Suppliers	TNZ M/4	Y	Y	N	Sieve Size	Percent Pe	assing	
TNZ M/4:AP40	Certificates						AP20	AP40	
	All Contractors					37.5mm		100	
	test results					19.0 mm	100	66 - 81	
						9.5 mm	55 – 75	43 - 57	
						4.75 mm	33 – 55	28 - 43	
						2.36 mm	22 - 42	19 - 33	
						1.18 mm	14 – 31	12 - 25	
						0.600 mm	8-23	7 – 19	
						0.300 mm	5 – 16	3 – 14	
						0.150 mm	0 – 12	0-10	
						0.075 mm	0 - 8	0 - 7	
						Fraction	Percent v	within AP40	
						19mm –	111 20	28 – 48	
						4.75mm		20 40	

June 2011

Testing			Inspection		Verification				
Phase	Test / Material Certificate Audit Frequency	Specification Reference	Contractor Y/N		Hold Point Y/N	Acceptance Criteria			Signed / Accepted / Date
						2.36mm	fines shall ushing resultity index ve a sand effraction of 5 mm sieve 3 or the fring a 0.42 ty index lest regate by	pass a 2.36mm istance test with a a above CB from test equivalent greater the aggregate shall have a clay action of the 5mm sieve shall	
CCC AP65	All Suppliers Certificates All Contractors	CSS Part 1: 26.2	Y	Y	N	Sieve Size Perc Pass 65.0 mm 100	cent sing		

Testing			Inspection	1	Verification				
Phase	Test / Material Certificate Audit Frequency	Specification Reference	Contractor Y/N	Engineer Y/N	Hold Point Y/N	Acceptance Criteria	Signed / Accepted / Date		
	test results					37.5 mm 60 - 90 19.0 mm 45 - 65 9.5 mm 30 - 50 4.75 mm 20 - 40 2.36 mm 10 - 28 1.18 mm 7 - 22 0.600 mm 5 - 16 0.300 mm 4 - 12 0.150 mm 3 - 8 0.075 mm 3 - 6 • CCC AP65 shall be free of organic matter • Less than 10% fines shall pass a 2.36mm sieve after a crushing resistance test with a 130kN load • CCC AP65 shall either have a sand equivalent greater than 25 or the fraction of the aggregate passing a 0.075mm sieve shall have a clay index less than 3 or the fraction of the aggregate passing a 0.425mm sieve shall have a plasticity index less than 5			
Premix concrete for kerb and channel	All Suppliers certificates	CSS Part 6: 4.3	Y	Y	N	Concrete (Normal) strength 20 MPa at 28 days, slump 75mm, nominal maximum aggregate 19mm, water content under 170 kg/m3			
100 dia uPVC Kerb entry	All Suppliers certificates	AS/NZS 1260: 1999	Y	Y	N	SN10, factory moulded			
100 dia uPVC SN10 pipe	All Suppliers certificates	AS/NZS 1260: 1999	Y	Y	N	SN10, 100mm uPVC			
First class topsoil	All Suppliers Certificates All Contractors	CSS Part 1: 29.1	Y	Y	N	Under 5% solid detritus, under 10% stone, both under 30mm diameter			

Testing			Inspection	n	Verification				
Phase	Test / Material Certificate Audit Frequency	Specification Reference	Contractor Y/N	Engineer Y/N	Hold Point Y/N	Acceptance Criteria	Signed / Accepted / Date		
	test results					 Under 25% clay, organic matter 7-20% Loose friable, well aerated, lightly processed pH 5.5-7.5 			
Medium grade bark mulch	All Suppliers Certificates All Contractors test results	CSS Part 1: 30.2	Y	Y	N	Under 25% wood chips, under 1% inorganic component, 100% between 11-40mm			
Construction		•	•						
Subgrade strength	Penetrometer test at 50 metre intervals, all Contractors test results	CSS Part 6: 11.6.4	Y	Y	Y	CBR greater than 7			
Kerb and channel stringline	Check height and location of string line at every peg on day poured	CSS Part 6: 4.4	Y	Y	Y	String 100mm behind kerb location and at design level			
Subbasecourse density	Nuclear Densometer test every 25 metres All Contractors test results	CSS Part 6: 4.2	Y	Y	Y	Minimum 2100 kg/m3 , 95% of readings exceeding 2150 kg/m3			
Subbasecourse level	Measure depth from string line every 50 metres and at all grade changes and TPs	CSS Part 6: 4.2	Y	Y	N	Finished levels within -25mm & +5mm of design			
Concrete placement	All Contractors test results	CSS Part 6: 4.3	Y	Y	N	Slump 75mm			
Kerb level	Check level of kerb every 50	CSS Part 6: 4.4	Y	Y	N	Finished level +/- 5mm of design			

Testing			Inspection Ven			Verification				
Phase	Test / Material Certificate Audit Frequency	Specification Reference	Contractor Y/N	Engineer Y/N	Hold Point Y/N	Acceptance Criteria	Signed / Accepted / Date			
	metres and at all grade changes and TPs									
Kerb alignment and location	Check alignment and location every 50 metres and at all TPs	CSS Part 6: 4.4	Y	Y	N	Location +/-10mm of design, max 5mm deviation, cumulative visible gaps 10mm over 3m straightedge				
Tree pit excavation	Check dimensions, subgrade condition in 1/5th tree pits	CSS Part 2: 8.4, Part 7: 6.6	Y	Y	Y	Minimum 1000mm deep, 750mm wide, subgrade loosened for 150mm all around				
Tree pit construction	Check finished level of filling, mulch area in 1/5th tree pits	CSS Part 2: 9.5.4, Part 7: 6.6	Y	Y	N	Finished surface +0mm, -0mm design Mulch extends 150mm outside tree stakes				
Trench excavation	Check dimensions of each fifth trench	CSS Pt 3: 8.7	Y	Y	N	Minimum 850mm to invert in drives, 750mm to invert in untrafficked areas without protection				
Pipe laying	Check fall to outlet of each fifth pipe	CSS Pt 3: 8.7	Y	Y	N	Invert level of pipe below property gully level				
Pipe haunching	Check depth of haunching of each fifth pipe	CSS Pt 3: SD 344/2	Y	Y	Y	150mm above and below pipe				
Trench backfill compaction	Clegg test each 1/5th trench. All Contractors test results	CSS Part 4: 13.3	Y	Y	N	Backfill exceeds Clegg Impact value of 35 in the commercial crossing, 25 in other areas				

APPENDIX XI INSPECTION & TEST SCHEDULE

Testing			Inspectio	n	Verif	fication	
Material /	Test(s) / Material	Specification Reference	Contractor	Engineer	Hold	Contract	Signed /
Construction	Certificate(s)		Y/N	Y/N	Point	Records	Completed
Phase	Required Frequency				Y/N		/ Date
Note that the l	below information i	is an example for selected phases only. Prepare inspection and test plans un	ique to the	project,			
incorporating	that project's qual	ity criteria for infrastructure and materials installed on that project.					
Materials – K	erb and channel						
CCC AP65	One sieve analysis/500m3	CSS Part 1: 26.2	Y	Y	N	Suppliers certificate Gradings	
Premix concrete for kerb and channel	Suppliers certificate/truck	CSS Part 6: 4.3	Y	Y	N	Suppliers certificate	
100 dia uPVC SN10 kerb entry	Suppliers certificate/delivery	www.ccc.govt.nz/webapps/approvedmaterials/frmAPRDetails.asp?APR_ID=58& Product Name=PVC	Y	Y	N	Suppliers Certificate	
Construction	 Kerb and channe 	el					
Subgrade strength	Penetrometer test at 50 metre intervals under kerb and channel	CSS Part 6: 11.6.4	Y	Y	Y	Metalcourse design checksheet	
Kerb and channel stringline	Check height and location of string line at every peg on each day string line used	CSS Part 6: 4.4	Y	N	N	Kerb and channel construction checksheet	
Subbasecourse density	Nuclear Densometer test every 10 metres	CSS Part 6: 4.2	Y	Y	Y	Kerb and channel construction checksheet	

Testing			Inspection	n	Verification		
Material / Construction Phase	Test(s) / Material Certificate(s) Required Frequency	Specification Reference	Contractor Y/N	Y/N	Hold Point Y/N	Contract Records	Signed / Completed / Date
Sub- basecourse level	Measure depth from string line every 20 metres and at all grade changes and TPs	CSS Part 6: 4.2	Y	Y	N	Kerb and channel construction checksheet	
Concrete placement	Slump test where mix appears dry	CSS Part 6: 4.3	Y	Y	N	Kerb and channel construction checksheet	
Kerb level	Check level of kerb every 20 metres and at all grade changes and TPs	CSS Part 6: 4.4	Y	N	N	Kerb and channel construction checksheet	
Kerb profile	Check profile at all hand boxed sections immediately after pour	CSS Part 6: 4.4	Y	N	N	Kerb and channel construction checksheet	
Kerb alignment and location	Check alignment and location every 20 metres and at all TPs	CSS Part 6: 4.4	Y	N	N	Kerb and channel construction checksheet	
Stormwater outlets	Check outlets at invert after placement	CSS Part 6: 4.5	Y	N	N	Kerb and channel construction checksheet	
Materials – T	ree pit		•	•	•		
First class topsoil	One sieve analysis, nutrient content and soil pH test/50m3	CSS Part 1: 29.1	Y	Y	N	Test results Suppliers certificate	
Bark mulch	One sieve	CSS Part 1: 30.2	Y	Y	N	Gradings	

Testing			Inspection	n	Verif	fication	
Material / Construction Phase	Test(s) / Material Certificate(s) Required Frequency	Specification Reference	Contractor Y/N	Engineer Y/N	Hold Point Y/N	Contract Records	Signed / Completed / Date
	analysis/50m3					Suppliers certificate	
Construction	– Tree pit						
Tree pit excavation	Check dimensions, subgrade condition of each pit	CSS Part 2: 8.4, CSS Part 7: 6.6	Y	Y	Y	Landscape construction checksheet	
Tree pit construction	Check finished level of filling, mulch area of each pit	CSS Part 2: 9.5.4 CSS Part 7: 6.6	Y	N	N	Landscape construction checksheet	
Materials – P	roperty stormwate	r pipes	•	•		•	
100 dia uPVC SN10 pipe	Suppliers certificate/delivery	www.ccc.govt.nz/webapps/approvedmaterials/frmAPRDetails.asp?APR ID=58 & Product Name=PVC	Y	Y	N	Suppliers Certificate	
TNZ M/4: AP20	One sieve analysis/50m3	TNZ M/4	Y	Y	N	Suppliers certificate Gradings	
Construction	 Property stormy 	vater pipes					
Trench excavation	Check dimensions once for each property	CSS Part 3: 8.7	Y	N	N	Property stormwater checksheet	
Pipe laying	Check fall to outlet for each line	CSS Part 3: 11.2	Y	N	N	Property stormwater checksheet	
Pipe jointing	Check each line doesn't leak	NZS 7643	Y	N	N	Property stormwater checksheet	
Pipe haunching	Check depth once for each property	CSS Part 3: SD 344/2	Y	Y	Y	Property stormwater	

Testing			Inspection	Inspection		Verification	
Material / Construction	Test(s) / Material	Specification Reference	Contractor Y/N	Engineer Y/N	Hold Point	Contract	Signed /
Phase	Certificate(s) Required Frequency		1/1	I/IN	Y/N	Records	Completed / Date
						checksheet	
Trench backfill compaction	Clegg test every 10 metres of trench, on all layers	CSS Part 3: 15.4	Y	N	N	Property stormwater checksheet	
Property stormwaters	Check all properties connected	CSS Part 6: 4.5	Y	N	N	Property stormwater checksheet	

APPENDIX XII QUALITY SYSTEM WORK PROCEDURE

CONTROL & INSPECTION OF PIPE SUBSOIL DRAIN CONSTRUCTION

1. Scope of this procedure

Subsoil drain construction other than perforated corrugated plastic pipe.

2. Responsibility & Actions

The site supervisor shall be an authorised drainlayer, where the pipe is laid in the legal road or shall be vested. Where the pipe is to be laid under a building consent, the site supervisor shall be a registered drainlayer.

The site supervisor shall be responsible for progressively inspecting the work to ensure it complies with the requirements.

The results of the inspection shall be recorded on the Pipe Subsoil Drain Construction Checksheet for defined sections of drain.

Inspection shall record the following:

- a) Pipe type and diameter.
- b) Trench width and depth.
- c) Bedding and filter material and depth.
- d) Measured grade.
- e) Joint details.
- f) Backfilling.
- g) Connections.

APPENDIX XIII ENGINEER'S H&S EXAMPLE CHECKSHEET

HEALTH AND SAFETY MANAGEMENT PLAN CONTRACTOR: DATE: PROJECT DESCRIPTION: The following should be documented: 1. Requirement **Project Description:** Met? Yes No Brief description of the scope of the work or services Summary of major activities and types of work Specialist tasks or procedures are documented and reference to safe work procedures and training documented Areas of project requiring special consideration are documented and procedural requirements are referenced: e.g. presence of public, traffic management, notifiable work, restricted work 2. Contractor's Health and Safety Structure and System: Names and positions of personnel with specific health and safety responsibilities are documented Position and name of the senior person who will liaise with the Engineer on health and safety issues is documented Name and position of the on-site supervisor is documented **3. Contractor's Induction and Safety Training:** Outline of the contractor's induction procedures for employees and subcontractors Register of personnel completing the induction programme Details of employee health and safety training relevant to the project. Copies of relevant certificates attached e.g. Code of Practice for Temporary Traffic Control, Cable Location, Confined Spaces Register of persons holding authorisations, permits, competency certificates, licenses etc required for the project

4.	Safe Work Practices and Procedures	
•	List of company safe work procedures relevant to the project	
•	Copies of safe work procedures, permits or notifiable work notices	
•	Details of project operations subject to work permits	
•	Work permit procedure documented	
•	Distribution list of people (including subcontractors) issued with safe work procedures	
5.	Noise	
•	Control measures and standards are documented with clear procedures on how to achieve the control	
6.	Hazard Management	
•	All hazards (existing and potential) associated with the project are documented on the hazard register form	
•	The hierarchy of controls has been considered (i.e. eliminate, isolate or minimise)	
•	Control measures are documented with clear procedures on how to achieve the control	
•	Evidence of employee and subcontractor training on control measures is included	
7.	Workplace Health and Safety Inspections	
•	Inspection team documented	
•	Frequency and type of inspection defined	
•	Checklists to be used are included	
•	Procedure for actioning inspection findings included	
•	Hazard reporting procedures documented and form included	
•	Specific areas targeted for inspections documented	
8.	Emergency Procedures	
•	Overall emergency plan and structure for the project	
•	Register of emergency equipment and locations	

Part 3: QUALITY ASSURANCE

•	Register of current qualified first-aiders		
•	Arrangements/coordination with other worksite occord emergency	cupants in event	
9.	Accident Reporting, Recording and Investigation	n	
•	Details of accident recording, reporting and investand procedures	stigation system	
•	Details of how accidents will be notified to OSH and	d Engineer	
•	Details of how accident statistics are to be c projects)	ompiled (major	
	Health and Safety Performance Monitoring	g (Major Projects)	
•	Details of how health and safety performance stat with the project are reviewed	istics associated	
•	Details of how monthly health and safety performation be compiled for review by Engineer	ance reports will	
•	Nature of health and safety performance informati employees on a regular basis	ion presented to	
•	Outline of auditing programme to evaluate the effective Health and Safety Management Plan	ectiveness of the	
10.	Health and Safety Management Plan Review		
	This Health and Safety Management Plan has b	een:	
	Reviewed by:		
	Approved by:	(Name/Position/Sign)	
	Contractor notified:	(Sign/Date)	
	Reviewed by:	(Date)	
	(Council)	(Name/Position/Sign)	

APPENDIX XIV ENGINEER'S GRAVITY PIPE TEST CHECKSHEET

Type of test		Air test	Hydrostatic test
	Visual inspection	Select test method (delete	e inapplicable)
Contract document	reterence		
	STANDARDS (to C	SS: Part 3)	
Nominal diameter ((mm)		
Pipe material and c	lass		
Location			
Overall length (m)			
SITE AND PIPELI	INE INFORMATION	I	
PROJECT TITLE		- -	
ASSET (sewer/sw)			
CONTRACTOR			

	Visual inspection	Select test method (delete inapplicable)				
Type of test		Air test	Hydrostatic test			
Reference	clause 14.2.3	clause 14.2.5	clause 14.2.4			
Performance	No leaks or	Pressure drop less than 2kPa	Water level does not drop			
measure	defects visible	(0.2m) over test period	over test period ¹			

TEST CRITERIA (provide before testing)

TEST RESULTS

Section tested	Length (m)	Test pressure ² (m)	Test period ³ (min)	Test Date	Pressure achieved (m) or loss (ml)	Pass / fail

- Note: 1) See Hydrostatic test table for allowable losses under 3.0m test head on reverse of sheet
 - 2) Determine hydrostatic test pressure using CSS: Part 3 clause 14.2.4. Test pressure for both types is a minimum of 3.0m.
 - 3) Obtain air test period from table in CSS: Part 3 clause 14.2.5 (reproduced on reverse of sheet). Hydrostatic test period is 5 mins.

Engineer	Signature	
Contractor Rep	Signature	
Council Rep	Signature	
Date plan accepted		
Date and time pipe test witnessed	Retest required	yes/no
NCR reference	Pipeline accepted	yes/no

1. Hydrostatic Testing

Allowable losses (ml) over a 5 minute test period

Conditions: Concrete pipe, where 30kPa hydrostatic test is required.

	Length of test section (m)							
Pipe diameter (mm)	5	10	15	20	30	40	50	100
225	28	56	84	113	169	225	281	563
300	38	75	113	150	225	300	375	750
375	47	94	141	188	281	375	469	938
450	56	113	169	225	338	450	563	1125
525	66	131	197	263	394	525	656	1313
600	75	150	225	300	450	600	750	1500

2. Air Testing

Length of air test required (min:sec)

Conditions: Maximum permissible loss in a concrete or ceramic pipe is 2kPa or 0.3 PSI.

		Length of test section (m)									
Pipe (mm)	diameter	10	20	30	40	50	60	70	80	90	100
	150	1:00	1:00	1:00	1:00	1:00	1:00	1:00	1:10	1:20	1:30
	200	1:00	1:00	1:00	1:10	1:20	1:30	1:40	1:50	1:50	1:50
	225	1:00	1:00	1:00	1:10	1:40	2:00	2:10	2:10	2:10	2:10
	250	1:00	1:00	1:20	2:00	2:20	2:30	2:40	2:40	2:40	2:40
	300	1:00	1:10	1:40	2:20	3:00	3:00	3:00	3:00	3:00	3:00
	375	1:20	1:50	2:40	3:40	3:40	3:40	3:40	3:40	3:40	3:40
	450	2:00	2:30	4:20	4:20	4:20	4:20	4:20	4:20	4:20	4:20

APPENDIX XV	ENGINEER'S CONCRETE PRESSURE PIPE TEST CHECKSHEET							
CONTRACTOR	 	ASSET (sewer/water)						
PROJECT TITLE								
SITE AND PIPELIN	E INFORMA	ATION						
Overall length (m)]	Location _				
Test water disposed o	t to							
Pipe material and class	SS]	Nominal d	liameter (mm)			
PRESSURE TEST ST		S (to CSS: Pa	rt 3)					
Contract document re	ference			-				
		elect test meth			12			
Type of test		pressure wate	r test		operating pressure water	test		
Reference	clause 14.3				14.3.2	1.0.2		
Performance measure	No pressui	No pressure loss			ared loss mm/hr not to e	exceed 0.3 x		
Test period	3 hrs			length m x dia mm 5 mins				
THRUST BLOCKS Block identifier	1	Bearing ca	unacity (l	·Pa)	Redesign required	New		
Diock identifier	Assum			verified	Kedesign required	design details		
Add rows as necessary								
TEST CRITERIA (pr	ovide before	e testing)		TEST R	RESULTS			
Section tested	Length (m)	Specified pressure allowable le	test or oss	Test Date	Pressure achieved (m) or measured loss (mm/hr)	Pass / fail		
Add rows as necessary								
				_				
Engineer	Signature		Contrac	ctor Rep_	Signature			
Engineer	Signature		Contrac	ctor Rep_	Signature			
Engineer Date plan accepted	C			ctor Rep_	Signature			
Date plan accepted Council Rep				ctor Rep_	Signature			
Date plan accepted Council Rep				ctor Rep_	Signature			
Date plan accepted Council Rep	nature				ū			
Date plan accepted Council Rep Sign Date and time pipe test	nature				ū			
Date plan accepted	nature witnessed:				ū			

APPENDIX X	VI	ENG	INEER'S I	PRESS	URI	E PIPE	TEST C	HECKSHEET	(
CONTRACTO	ıR			ASSET	Γ(se	wer/wa	ter)			
PROJECT TIT										
SITE AND PIF							Location			
Overall length Test water disp	osed o	of to:					Location _			
Pipe material a	nd cla	ss:								
Nominal diame	eter (m	nm): _								
			_ ~							
PRESSURE TI										
Contract docum	nent re	eterence:								
		Select test	method (de	oloto in	anni	licable)				
Type of test	-		rebound n		иррі			essure method	ĺ	
Material		$PE \le DN3$		10011001			, GRP, PV		-	
Reference	clause 6.3.4.4					use 6.3.4.				
Performance		Pressure rises or remains static			tic	Ma	ake up wa	ter $Q \le 0.14LD$	H1	
measure										
Test pressure	(m)	1.25 x ma	x operating	pressu	re b	ut less t	than 1.25	x rated pressure		
	~~									
THRUST BLC		•	· (ID)		-			. 1		
Block		ring capac			1	design	New d	esign details		
identifier Add rows as	Assu	ımed	Site verif	iea	rec	quired	neu			
necessary										
necessary			<u> </u>							
CONSTANT F	RESS	URE MET	THOD			Ren	ıove redur	ndant test metho	od	
TEST CRITER	IA (pi	rovide befa	ore testing)				ST RESUI			
Section tested		Q				Test		water used		/
		(l/hr)	pressu	re (m)		Date	(l/hr)		fail	
PRESSURE R	EDOL	INID METI	IOD			Don		dant to at moth	a d	
TEST CRITER							iove reaur ST RESUI	ıdant test metho TS	м	
Section tested	$\mathbf{u}_{\mathbf{A}}(p)$	Speci:	<u> </u>	Test	P	1	ΔV^2	Pressure	Pass	
Section tested		_	ure (m)	Date	*	60		plot ²	fail	,
		<u> </u>	()							
Note 1) Provi	de deta	ails of this c	alculation.				I	1		
2) Provi	de tim	e/pressure i	readings and	d graphe	ed re	esults to	confirm to	est details, as de	tailed in	
	2566.2		<i>8</i>	8 1						
Engineer				Co	ntra	actor R	kep			_
_		Signature						Signatur	e	
Date plan accept	ed _									
Council Rep		C: on otrono								
	,	Signature								
Date and time pi	ne test	t witnessed	1							
Retest required	Pe test	yes/no	•							
Pipeline accepte	d	yes/no								
NCD reference		<i>y</i>								

APPENDIX XVII CONSTRUCTION CHECKSHEET

CONTRACT/JOB:	DATE:	
DRAIN LOCATION:	_	
Task	Acceptance Criteria/Test Frequency	Task/Completion Signature/Comment
Drawings and specifications checked for requirements		
Pipe material type class diameter		
Filter material specification grading		
Trench alignment check grade (normal min 1:100) width depth		
Bedding min depth 75mm sockets not bearing	Yes/No	
Pipe laying sockets uphill joints clean, invert flush joints as detailed rings required isolated from surface water		
Backfill material specification grading		
Backfill placement layer depth compaction		
Connections as per design location		
Arising NCR: All tasks defined above have been satisf	actorily completed to the sta	andards required:
Contractor:		
		(Sign/Date)

APPENDIX XVIII CONSTRUCTION CHECKSHEET

ACTIVITY — BASECOURSE STRINGING					
CONTRACT/JOB: ROAD LOCATION:	DATE:				
Refer to diagram on back of this shee	et for measuring diagram				

Ch.	L	C	R	Ch.	L	C	R
	l						

APPENDIX XVIV CCTV REQUIREMENTS

All sewer and stormwater reticulation services with pipe diameters 150mm or greater to be vested in Council shall be inspected with CCTV videoing. Inspection records shall comply with NZWWA "New Zealand Pipe Inspection Manual" and Council's CCTV specification.

All data and operator analysis shall be collated on an indexed DVD and a copy supplied to Council along with log sheets for approval. The CCTV work is to be carried out at the time of practical completion of works. Where defects in sewer, stormwater or water reticulation are noted during the defects liability period Council may require a further CCTV video inspection be undertaken to inspect the defects. The CCTV data is required to be submitted and approved before Council issue of a S224 Certificate or Engineers' Practical Completion Certification.

The Council specifications sets down requirements for Council's new Asset Management System software and can be obtained from Council.

APPENDIX XVV S224 ENGINEERING APPROVAL DATA CHECKLIST

Selwyn DISTRICT COUNCIL	
RESOURCE CONSENT #.	DATE://
SUBDIVISION NAME	-
LOCATION:	

	INITIAL – ACCEPTANCE	DATE
A a Dwille Calcadula	OR N/A	
As Built Schedule		
AS Builts Digital Plan (to CAD person)		
Benkleman Beam test		
CCTV diskette		
CCTV log (to CAD person)		
CCTV stormwater log (to CAD person)		
Clegg Hammer Footpaths/entrances		
Fill Certificate		
Fill Certificate to records (digital to GIS)		
Nuclear density test		
Producer statement - engineer		
Producer statement - contractor		
Stormwater Compliance Certificate		
Stormwater Management Plan		
Sewer reticulation pressure test		
Street names provided		
Streetlighting field check		
Vehicle crossings built or bond		
Water meter schedule		
Water reticulation chlorination test		
Water reticulation pressure test		