



Infrastructure Report

TWO CHAIN ROAD LTD.

**TWO CHAIN ROAD INDUSTRIAL PARK PLAN CHANGE
PROJECT 15010**



ISSUE FINAL – 6 APRIL 2022

Contents



1. INTRODUCTION	3
1.1. Purpose.....	3
1.2. Limitations.....	3
2. SITE OVERVIEW	4
2.1. Site Description	4
2.2. Groundwater & Bores	4
2.3. Existing Infrastructure	4
2.4. Drainage Features.....	5
2.5. Geotechnical Investigation.....	5
3. STORMWATER.....	6
3.1. Existing Stormwater Management.....	6
3.2. Stormwater Disposal.....	6
3.3. Flood Risk.....	6
4. WASTEWATER.....	8
4.1. Existing Network	8
4.2. Existing Network Capacity	8
4.3. Proposed Wastewater Reticulation.....	8
5. POTABLE WATER.....	9
5.1. Existing Reticulation	9
5.2. Water Demand.....	9
5.3. Network Capacity	9
6. POWER / TELECOMMUNICATIONS.....	10
6.1. Power	10
6.2. Streetlighting.....	10
6.3. Telecommunications.....	10
7. ROADING.....	11
7.1. Road Layout.....	11
7.2. Road Stormwater Drainage.....	11
8. EARTHWORKS.....	12
8.1. Bulk Earthworks.....	12
9. SUMMARY & CONCLUSION	13
 APPENDIX A WSP Wastewater Network Capacity Assessment	
APPENDIX B WSP Water Supply Network Capacity Assessment	
APPENDIX C Site Plans	

QUALITY ASSURANCE

PREPARED BY	CHRIS SEXTON	CIVIL ENGINEER		25 AUGUST 2021
REVIEWED & APPROVED BY	TIM MCLEOD	SNR CIVIL ENGINEER		6 APRIL 2022

1. Introduction

1.1. Purpose

Inovo Projects Ltd has been engaged by Two Chain Road Ltd to complete an Infrastructure Assessment for a proposed industrial development at 7-183 Two Chain Road, located to the southwest of the Rolleston IZone Industrial Park. This Infrastructure Assessment has been prepared in support of a proposed Plan Change application for development of the site for industrial use (Business 2A zoning).

The purpose of this report is to provide information on;

- Existing infrastructure around the site
- Proposed infrastructure for the development
- Conformance to national standards, Selwyn District Council's (SDC) policies and best practices relating to subdivision development, in particular:
 - Waterways, Wetlands and Drainage Guide (Christchurch City Council)
 - Selwyn District Council's *Engineering Code of Practice* (SDC ECOP)
 - NZS4404:2010 Land Development and Subdivision Infrastructure

1.2. Limitations

This report may not be reproduced, in whole or in part, without our prior written approval. This report has been prepared for the purpose stated in the report and may be relied upon for that purpose only. Assumptions made in the preparation of the report are as expressly stated in the report or set out below.

Where information has been supplied to us for the purpose of the report by another party, this information is believed to be reliable but we can accept no responsibility if this should prove not to be so.

2. Site Overview

2.1. Site Description

The Two Chain Road Plan Change site (the 'Site') is approximately 98 ha in area, and is located to the southwest of the Rolleston IZone Industrial Park & Business Hub. The site is bounded by Two Chain Road to the north, Walkers Road to the west, the Main South Line railway corridor / State Highway 1 to the south, and the Midland Line railway to the east.

The site is currently zoned rural inner plains, with the land to the southwest being Rural Outer Plains with special designation for Rolleston Prison, Residential Living Z and Residential Living 1 to the southeast (across SH1), Business B2 to the northeast (across the Midland Line), and Rural Inner Plains to the northwest.

The site is typically gently sloping (1:200) from northwest to southeast, that is from Two Chain Road towards State Highway 1. Part of the Paparua Stockwater Race network crosses the site at the western end, and a second minor branch enters and terminates within the site boundary at the eastern end.

The site covers 13 separate land parcels used mainly as small farmland holdings. The site has been used for farming purposes for at least the last 80 years and is currently covered in a variety of pasture and shelter belts.

2.2. Groundwater & Bores

Well logs from the Environment Canterbury (ECan) database indicate that the depth to groundwater in the area is approximately 15-20m.

There are 7 bores on the site with recorded use as stock water and domestic supply (information from Canterbury Maps). Table 1 summaries the bore depth, diameter and recorded usage.

Table 1 – Well Data

Address	Well No.	Depth	Diameter	Recorded Use
7 Two Chain Rd	M36/4334	40m	150mm	Domestic Supply
15 Two Chain Rd	M36/4655	25m	51mm	Stock Supply
77 Two Chain Rd	M36/0084	35m	150mm	Domestic Supply
113 Two Chain Rd	M36/0010	82m	51mm	Not Used
93 Two Chain Rd	M36/3090	41m	150mm	Domestic & Stockwater
113 Two Chain Rd	M36/7457	35m	150mm	Domestic & Stockwater
183 Two Chain Rd	M36/5525	47m	150mm	Irrigation, Domestic Supply

There are 2 recorded community supply wells neighbouring the site with drinking water protection zones which overlap the site boundary. One is located within the Rolleston Prison site to the west (bore M36/4459, 55.5m deep) and the other down-gradient on the southern side of SH1 (bore M36/0026), near the end of George Street cul-de-sac. Bore M36/0026 in George Street was decommissioned along with a reservoir in 1996 as part of town water supply reticulation upgrade works and is classified on Canterbury Maps as "buried/unlikely still exists". The site area does not fall within the Christchurch Groundwater Recharge Zone.

2.3. Existing Infrastructure

There is limited SDC infrastructure servicing the site with the exception of DN63mm potable water submain at the eastern end of the site (before crossing to the northern side of Two Chain Road). There is a Ø150mm water main located to the northeast of the site at the corner of Railway Road and Jones Road (across the Midland Line railway), and an existing Ø150mm water supply main in Walkers Road. Existing infrastructure within the neighbouring industrial subdivisions to the northeast can be extended to the proposed development. Further discussion of water supply is found in Section 5.

An existing Ø225mm gravity sewer main is located at the corner of Railway Road and Jones Road which conveys wastewater eastwards to the George Holmes pump station (located at the corner of Jones Road and George Holmes Road). From this pump station wastewater is pumped directly to the 'The Pines' Wastewater Treatment Plant (WWTP) to the southwest along Burnham School Road. Further discussion of sewer infrastructure is found in Section 4.

2.4. Drainage Features

The site is gently sloping at 1:180 to 1:200 gradient to the south-southeast. The ground surface is slightly undulating with shallow flood channels crossing the sites as is typical of the Canterbury Plains.

A branch section (lateral) of the Paparua Stockwater Race network crosses the site from north to south, passing through a culvert under Two Chain Road approximately 275m northeast of Walkers Road, then running parallel to a fenceline across the site before deviating slightly and passing through a culvert under the Main South Line railway and Main South Road (SH1). A second minor lateral enters and terminates within the site at two locations further to the east along Two Chain Road at No. 15 (Lot 2 DP27804) and No. 25 Two Chain Road (Lot 1 DP27804). These minor laterals terminate in soakpits discharging to ground within the site. A section of main channel of the Paparua Stockwater Race network (Railway Road branch) curves around the eastern boundary of the site (but outside the site boundary), before passing through a culvert under the Main South Line and the Main South Road (SH1).

The Main South Railway along the southeast boundary forms a barrier to overland flood flows. With the exception of the two water race culverts mentioned above, no evidence has been found of drainage culverts passing under the Main South Railway line (any culverts, if they do exist, have become overgrown and blocked due to lack of use). Borrow pits excavated immediately up-slope of the railway line serve as means of discharge of stormwater runoff to ground.

2.5. Geotechnical Investigation

A geotechnical investigation report has been prepared by Coffey Tetra Tech to provide information on the underlying soil conditions. The investigation included a desktop review and site walk over.

A summary of the ground profile provided by Coffey Tetra Tech is as follows:

- 0.3m topsoil, overlying
- 0.5 to 2m sandy silt loam, overlying
- Sandy GRAVELS to depth

3. Stormwater

3.1. Existing Stormwater Management

Discharge of stormwater to ground is common practice in the Rolleston area due to free-draining nature of the underlying gravels. As such, Rolleston has little stormwater reticulation network as most stormwater is discharged directly to ground via soakage pits and basins. Recent subdivisions near to the proposed rezoning, such as the Stonebrook residential subdivision to the south, and IZone and IPort Business Parks to the north and northeast have utilised soakage to ground for stormwater management.

3.2. Stormwater Disposal

Geotechnical investigations for nearby sites have indicated good drainage characteristics and that discharge to ground is feasible, as typical of the Rolleston area. As with all ground soakage systems, the efficiency can decrease over time. However, by adopting a conservative approach to the design of the systems, ensuring that there are adequate options for future upgrading and making allowance for secondary flows, ground soakage systems can provide a cost-effective long-term solution to stormwater disposal.

Individual sites will discharge primary runoff from rooves and hardstand areas directly to ground via on-site soak pits. The soak pits will be constructed as part of building consent process at building stage. Soakpits for individual sites will be sized to deal with storms up to the 2% AEP 1 hour event. All drainage infrastructure and soakpits associated with future roads will be constructed as part of any future subdivision and will be vested in SDC. Soakpits for road drainage will be sized to deal with storms up to the 10% AEP 10-minute event.

In general, the first flush stormwater runoff (i.e., first 15 to 25mm of any storm) is more polluted than the stormwater runoff from the remainder of the storm event. The first flush is generally treated using treatment systems which provide higher levels of contaminant removal than the treatment systems required for subsequent stormwater runoff. This first flush can be treated through a swale or infiltration basin or proprietary stormwater treatment devices such as hydrodynamic separators.

Stormwater runoff from large rainfall events which exceed the first flush capacity can be discharged directly to ground using rapid infiltration trenches or soakpits. Ponding areas may be required to temporary store runoff from large hardstand areas where runoff rate exceeds infiltration capacity of rapid infiltration trenches or soakpits.

Adequate measures would need to be implemented to ensure the effects of the discharge on the underlying groundwater are reduced to an acceptable level using suitable treatment and attenuation devices as required. Resource consent for stormwater discharge to ground from the plan change sites will be obtained from Environment Canterbury (ECan) at the subdivision consent stage. Any consents required from ECan for stormwater discharge from roads to vest will be transferred to SDC as required.

Flows in excess of the capacity of the primary system can be directed to the roads which will act as secondary flow paths to safely convey stormwater through the development.

It is expected that all stormwater will be able to be permitted to discharge to ground and that from a stormwater perspective, the plan change can be supported with areas set-aside if required, for stormwater treatment and attenuation as outlined above.

3.3. Flood Risk

As is typical of the Canterbury Plains, overland flow generated by continuous heavy rain or thunderstorms that the land cannot absorb becomes concentrated in shallow channels that cross the plains. Shallow channels can be observed crossing the site and continuing to the Main South Railway embankment along the southeast boundary which forms a barrier to overland flow (no evidence has been found of drainage culverts passing under the Main South Railway line).

Flood modelling maps for the Selwyn region showing the extent and depth of potential flooding during a 200-year ARI or 0.5% AEP rainfall event are available to view on SDC's website. **Figure 1** below shows the predicted flooding for the subject site.

The predicted floodwater depth is generally less than 0.5m except where existing former borrow pits or soak holes excavated to facilitate soakage to ground indicate ponding depths of 1.5m to 3m, or where water ponds up against the Main South Railway embankment. It is noted that SDC flood model does not take into account infiltration or discharge to ground via soakpits. In practice, overland flow across the railway line is unlikely to occur and floodwaters will enter soak pits / former borrow pits and discharge to ground.



Figure 1 – Flood Modelling from SDC Flooding Map

A more detailed flood risk assessment will be carried out at subdivision consent application stage as required by Section 106 of the Resource Management Act. Overland flow from upstream catchments will be considered to ensure that any potential adverse stormwater effects can be appropriately mitigated and minimum floor level rules set at the time of subdivision development.

In general, ground levels for lots will be set above internal road levels so the roads act as secondary flow paths to safely convey floodwaters to the downslope side of the site.

4. Wastewater

4.1. Existing Network

The site is currently not connected to the Rolleston wastewater network. There is existing gravity wastewater infrastructure in Jones Road to the northeast (across the Midland rail line), and running past the southwest end of the site in Walkers Road. Existing dwellings on the site discharge via septic tanks and on-site wastewater disposal fields.

4.2. Existing Network Capacity

Refer to the Wastewater Network Capacity Assessment prepared by WSP attached as Appendix A for an assessment of the capacity of the existing gravity and network. WSP have developed a network capacity model for SDC and have completed an analysis of the impact of the proposed site development on the existing network. This analysis also considered other proposed plan changes in the Rolleston and West Melton areas to ensure that sufficient capacity is available within the network or to find any potential areas where upgrades would be required in order to service the proposed Two Chain Road development.

Discharge from the development was assessed by WSP to have a ADWF of 5.9 L/s and PWWF of 14.2L/s based on average dry weather flow of 0.06 L/s/ha using historic flow records from the George Holmes pump station which services the IZone and IPort industrial catchment area.

WSP investigated connection into the existing SDC wastewater network at 2 locations, one being an existing manhole in Jones Road (Asset ID 78634), and the other being through a manhole on Walkers Road (Asset ID 98559).

Analysis by WSP indicates capacity constraints in the gravity network downstream if the development were to connect via Manhole 98559 in Walkers Road. This would result in surcharging during dry weather flows and flooding during wet weather flows.

Analysis by WSP indicates that servicing the development via an existing manhole (ID 78634) in Jones Road and discharging via gravity to the George Holmes pump station has sufficient capacity for the proposed development, while also considering other potential plan changes within the Rolleston area.

Refer to the Wastewater Network Capacity Assessment prepared by WSP attached as Appendix A for an assessment of the capacity of the existing rising main network to The Pines WWTP. The Pines WWTP has not been assessed if there is sufficient capacity to accept flow from this development, but it is understood capacity at the Pines WWTP is scheduled for upgrades within the LTP to provide capacity for up to 120,000 person equivalents.

4.3. Proposed Wastewater Reticulation

Servicing the development from the existing manhole in Jones Road via gravity is possible for approx. 1/3 of the site if the gravity system is extended from Johns Road along Two Chain Road. However, due to the shallow gradients either a lift station or low-pressure sewer would be required to service the remainder of the site.

Servicing the development via gravity drainage to Walkers Road is not feasible due to the shallow depth of the existing sewer and the topography falling from Walkers Road to Jones Road. Either a lift station or low-pressure sewer would be required to discharge to existing gravity sewer in Walkers Road.

From a wastewater perspective, the plan change can be supported with new infrastructure servicing the plan change area as outlined above.

5. Potable Water

5.1. Existing Reticulation

The Rolleston township reticulated supply extends along Two Chain Road as a Ø63mm sub-main from Jones Road to halfway along the proposed block on the northern side of Two Chain Road. There is a Ø150mm uPVC water main located to the northeast of the site at the corner of Railway Road and Jones Road (across the Midland Line railway). This changes to a Ø300mm mPVC main at the intersection of Jones Road and Izone Drive some 180m to the east.

There is also a Ø150mm uPVC watermain in Walkers Road extending from the Dunns Crossing/Walkers Road/SH1 intersection to part way along the eastern side of Walkers Road which is the main water feed to the Rolleston Prison site.

5.2. Water Demand

Water demand for the site is based on peak design flow rate is 1 litre per second per hectare (1 L/s/ha) in accordance with 'NZS4404:2010 *Land Development and Sub-Division*' and the SDC Engineering Code of Practice. Demands from the proposed plan change site would result in a peak demand of 98.3 L/s for consumptive use.

The water supply demands for firefighting are based on the SNZ PAS 4509:2008 FW4 classification for buildings. FW4 requires that 50L/s is provided by a hydrant within 135m of the hazard, with an additional 50 L/s required (total 100L/s) from 3 additional hydrants (4 total) within 270m of the hazard. In such instances where the required fire water classification exceeds FW4, additional on-site storage will need to be provided by the building owners to ensure sufficient capacity for firefighting. Firefighting classification of individual buildings and fire water storage requirements would be determined and managed at time of building consent.

5.3. Network Capacity

Refer to the Water Supply Network Capacity Assessment prepared by WSP attached as Appendix B for an assessment of the upgrades required to the SDC water supply network to service the plan change area. The assessment carried out by WSP included demands on the system for the current proposed plan change for a 27 Ha extension of the IPort Business Park.

WSP considered options for connection to the existing network via both Jones Road (300mm dia. Main) and Walkers Road (150mm dia. Main). Sufficient capacity is available for the development to be serviced from Jones Road with network upgrades (upsizing reticulation pipes) near the IZone water supply headworks site. The second option considered a connection from the existing main within Walkers Road, however this resulted in high headloss within the existing main and widespread low pressure within the residential zone south of the highway. Therefore, connecting via Jones Road is the preferred option.

From a water supply perspective, the plan change can be supported with an extension of existing infrastructure and some internal network upgrades to service the plan change area.

6. Power / Telecommunications

6.1. Power

Power will be provided to all allotments to utility company and industry standards. All network and reticulation cabling will be installed underground. Transformer kiosk sites will be located at locations approved by the utility company and SDC.

The nearest substation is the Rolleston Zone Substation located at the corner of Burnham School Road and Dunns Crossing Road. The nearest transformer kiosks are located at 10 Railway Road and outside Rolleston Prison on Walkers Road. There are existing overhead 11kV powerlines and an underground 11kV cable running along the southern side of Two Chain Road, and existing 11kV underground cables running along the western side of Walkers Road that loop into the transformer located at Rolleston Prison. There are also overhead lines running along the western side of Walkers Road that carry both 11kV and 33kV power. There is also an overhead 11kV supply which crosses over SH1 and the Main South railway corridor and terminates within the plan change site.

Full appraisal of the network extension requirements will be carried out by the network provider once the Plan Change approval has been obtained. Orion have advised they have already started planning network upgrades and associated distribution reinforcement to service the residential and commercial development in Rolleston, including a new Zone Substation at Burnham. There is an estimated 18-24 months turnaround time from initial planning to approval and construction of the required electrical infrastructure upgrades to supply the plan change sites.

From an electricity supply perspective, the plan change can be supported with an extension of existing infrastructure and provision of local transformers to service the plan change area.

6.2. Streetlighting

Streetlighting will be provided to roading and reserves in accordance SDC engineering standards where required. The applicant will provide a streetlight style consistent with styles used elsewhere in Rolleston.

6.3. Telecommunications

Telecommunications will be provided to all sites in the form of fibre optic network installed to utility company and industry standards. The existing fibre network in Jones Road can be extended to the subject sites and distributed to individual allotments. All network and reticulation cabling will be installed underground.

7. Roding

7.1. Road Layout

The proposed primary roading layout is yet to be developed, however site access will be likely be developed off Two Chain Road and Walkers Road.

Access points and internal roading layouts will be determined during the subdivision design stage in consultation with SDC.

7.2. Road Stormwater Drainage

Stormwater runoff within road corridors will be conveyed via kerb and channel into appropriately spaced sumps or roadside swales. All sumps will have trapped and/or inverted outlets, and connected to the piped stormwater network or conveyance swales. The road corridor will be used as overland flow paths to direct stormwater runoff when the drainage network is at full capacity.

8. Earthworks

8.1. Bulk Earthworks

The topography of the existing site is generally sloping to the south/southeast at an average gradient of 1:200 and approximately 7m total elevation change across the site (refer to LiDAR contour plans included in Appendix C)

Bulk earthworks design will be determined at detail design stage. Consideration will be given to providing overland flow paths along internal roads to maintain existing flow patterns.

To avoid carting material off-site earthworks will be designed to achieve a cut/fill balance across the site. Any filling operations exceeding 300mm depth will be carried out in accordance with NZS4431:1989 *Code of Practice for Earthfill for Residential Development*. It is envisaged that material won from site, will be sufficient to use as structural engineered fill.

All earthworks will be carried out in accordance with principles outlined on the Environment Canterbury's *Erosion Sediment Control Toolbox* to minimising the adverse effects of erosion and sedimentation during construction. Dust generation from earthworks operations is expected to be no worse than if paddocks were cultivated as part of normal farming operations.

9. Summary & Conclusion

Primary stormwater runoff from rooves and hardstand areas will be discharged directly to ground via soakpits or drainage trenches. The development will be designed to ensure that secondary flow will safely drain from buildings via the internal roads.

Wastewater from the site can be connected to the existing SDC gravity sewer by extending the network in Jones Road under the Midland railway line and southwest along Two Chain Road. At least two thirds of the site will require either low pressure sewer or a lift station to discharge into the gravity network. Gravity discharge to Jones Road will pass through to the George Holmes pump station which then pumps directly to The Pines Wastewater Treatment Plant.

Potable water reticulation can be provided by extending the existing SDC network in Jones Road under the Midland railway line and southwest along Two Chain Road. Additional upsizing of water mains on Izone Drive to the IZone headworks will be required to ensure adequate supply is available for the proposed development.

Existing electricity and fibre broadband networks neighbouring the site can be extended to service the proposed plan change area. Electricity and telecommunications will be provided to all sites to utility company and industry standards. All cables within the development sites will be installed underground and kiosks will be constructed on separate individual lots.

From an infrastructure perspective, the plan change can be supported by either the extension of existing infrastructure from neighbouring subdivisions or the provision of new/upgraded water supply and wastewater infrastructure to service the development area.

APPENDIX A | WSP Wastewater Network Capacity Assessment

Project Number: 3-C2333.00

Rolleston Two Chain Road Plan Change

27 July 2021

CONFIDENTIAL



Wastewater Network Capacity Assessment

Contact Details

Mark de Lange

WSP
12 Moorhouse Avenue
Christchurch 8011
+64 3 363 5400
+64 27 272 5854
mark.delange@wsp.com

Document Details:

Date: 26 July 2021
Reference: 3-C2333.00
Status: Final

Prepared by



Mark de Lange
Engineer Water

Reviewed by



Charlotte Mills
Principal Engineer

Approved for release by



Amy Harrod
Head of Water - Christchurch



Document History and Status

Revision	Date	Author	Reviewed by	Approved by	Status
0	16/07/2021	MdL	CM	AH	Final
1	26/07/2021	MdL	CM	AH	Final

Revision Details

Revision	Details
1	Revision as per comments form Rolleston Industrial Developments Ltd.



Contents

Disclaimers and Limitations.....	1
1 Summary	2
2 Assumptions	2
2.1 General.....	2
2.2 Scenario Specific	3
2.3 Model Updates.....	4
2.4 Additional Development Areas	4
3 Wastewater Servicing Options	6
4 Modelling Methodology	7
5 Modelling Results.....	8
5.1 Option 1 - Service via Jones Road	8
5.2 Option 2 - Service via Walkers Road	10
6 Conclusions.....	13
7 Limitations.....	13

List of Figures

Figure 2-1: Wastewater Network Overview.....	3
Figure 2-2: Iport Block Assumed Connection Point	5
Figure 2-3: Holmes Block Assumed Connection Point	5
Figure 3-1: Two Chain Block Connection Point Options	7
Figure 5-1: Long section at PDWF in the from manhole Asset ID 78634 to George Holmes PS. Predicted levels in the current system without the Two Chain Block is shown by the red line.....	9
Figure 5-2: Long section at PDWF in the from manhole Asset ID 98559 to Burnham School Road PS. Predicted levels in the current system without the Two Chain Block is shown by the red line.....	11
Figure 5-3: Long section at PWWF in the from manhole Asset ID 98559 to Burnham School Road PS. Predicted levels in the current system without the Two Chain Block is shown by the red line....	12

List of Tables

Table 2-1: Calculated Flows for the Plan Change Block.....	4
Table 2-2: Calculated Flows for West Melton Plan Change Areas	6

Disclaimers and Limitations

This report ('**Report**') has been prepared by WSP exclusively for Rolleston Industrial Developments Ltd. ('**Client**') in relation to the Two Chain Road Plan Change in Rolleston ('**Purpose**') and in accordance with the scope of works provided via email on 6 July 2021. The findings in this Report are based on and are subject to the assumptions specified in the Report and other model modelling reports addressed to Selwyn District Council. WSP accepts no liability whatsoever for any reliance on or use of this Report, in whole or in part, for any use or purpose other than the Purpose or any use or reliance on the Report by any third party.

1 Summary

WSP was engaged by Rolleston Industrial Developments Ltd. to complete a wastewater network capacity assessment to support the plan change of 98.3 ha of land on Two Chain Road in Rolleston to industrial. This assessment was completed using the network hydraulic model that WSP has developed for Selwyn District Council (SDC).

The assessment found that the existing gravity network in the George Holmes pump station catchment, and the pump station, have sufficient capacity for the predicted increased flows. Based on this, the wastewater network has capacity to allow for the rezoning of this land for the plan change application.

2 Assumptions

2.1 General

- The recently updated Eastern Selwyn Sewerage Scheme (ESSS) hydraulic model was used as the base network for this assessment. All modelling was completed in InfoWorks ICM v6.0.9 (WSP model reference: [dcapa500app57.corp.pbwan.net/SDC Wastewater Models](http://dcapa500app57.corp.pbwan.net/SDC%20Wastewater%20Models)). In this model, network asset data and contributing population were recently updated however updates to the calibration are required for select areas. The limitations applying the uncalibrated model were considered in this assessment and are detailed later in this report.
- Other recent land use changes and developments that were considered in this assessment include the Iport 27 ha Extension (industrial), the Holmes Block (residential) and known West Melton plan changes available on SDC's website. Figure 2-1 presents an overview of the wastewater network that may receive flows from the proposed industrial area on Two Chain Road, identifying the location of the George Holmes and Burnham School Road pump stations. The location of all development blocks considered in this assessment are also indicated on Figure 2-1.




Figure 2-1: Wastewater Network Overview

- To conservatively represent flow conditions the highest observed rate of groundwater ingress to the wastewater collection system was assumed. This high groundwater was observed in June 2014, affecting the communities of Prebbleton, Lincoln and Springston and was applied in the model as a constant baseflow.
- The model has been run with 1 in 5-year ARI 12-hour design event to replicate wet weather flow (WWF), as this was previously determined to be the critical storm duration for the ESSS system. To truly understand the impact of rainfall, a variety of rainfall events would need to be considered. However, there are many variables to consider, including but not limited to, the annual exceedance probability (AEP), intensity, duration and timing of the event (in relation to flows in the wastewater system). Comprehensive modelling of a variety of design rainfall events has not been conducted as part of this query.

2.2 Scenario Specific

The approach to calculating the design flow from the Two Chain Block is consistent with what was used for the Iport 27 ha Extension assessment. Flow records from the George Holmes pump

station for the period 1 January 2019 – 31 December 2019 were assessed, and the following was determined:

- Average dry weather flow per hectare = 0.06 L/s/ha;
- Peak flow peaking factor of 2.4;
- No wet weather response was observed.

These parameters were then used to calculate flows for the Two Chain Block which are presented in Table 2-1.

Table 2-1: Calculated Flows for the Plan Change Block

Plan Change Block	Area (ha)	Calculated ADWF (L/s)	Calculated PWWF (L/s)
Two Chain Road	98.3	5.9	14.2

2.3 Model Updates

As was noted above, the recently updated ESSS network model was applied for this assessment. As several calibration issues were identified in the model update and have yet to be resolved, the following adjustments have been made in order to apply the model for study:

- During the update it was found that modelled volumes in the Wilfield pump station catchment were underrepresented compared to observed data, which also resulted in the underprediction of volumes at the downstream Gainsborough pump station (terminal West Melton pump station). As a temporary fix the contributing population in the Wilfield pump station catchment was increased to match observed volumes. This resolved volume errors at both pump stations.
- During the update it identified that the pumps at the George Holmes pump station appear to be have been replaced since the original model was built. The model has a peak pump rate of approximately 70 L/s while observed data has a typical flowrate of approximately 90 L/s, with peak flowrates up to 135 L/s. As a temporary fix the main pump at the George Holmes pump station was replaced with a fixed pump with a discharge of 90 L/s.

2.4 Additional Development Areas

As was highlighted above, the Iport 27 ha Extension (industrial), the Holmes Block (residential) and known West Melton plan changes were considered as part of this assessment. The following presents how each was represented in the model for this assessment.

Iport 27 ha Extension

As part of the *Iport 27 ha Extension Wastewater Capacity Assessment* completed by WSP in December 2020, a design flow of 3.9 L/s was calculated for this development block. For the current study this flow was applied as a constant inflow to manhole 658244 at the intersection of Transportation Drive and Freight Drive. This load point is indicated on Figure 2-2, being downstream of both load points assessed in the December 2020 report.




Figure 2-2: Iport Block Assumed Connection Point

Holmes Block

For the *Rolleston West Plan Change Wastewater Capacity Assessment* completed by WSP in November 2020 both a dry and wet weather flow scenario were run to assess impacts on the network. For the dry weather flow scenario, a population of 3105 was added to the model, assuming a per capita wastewater flow of 220 L/h/d and applying a design wastewater discharge profile with a peaking factor of 2.5 (as per SDC's Engineering Code of Practice). The wet weather scenario was run the with a calculated design flow of 39.5 L/s applied as a constant flow. No contributing area or population for the plan change area was added as these are accounted for in the flow applied.

For the current assessment it has been assumed that all flows from the Holmes Block discharge by gravity to manhole 43404 on Dunns Crossing Road. This load point is indicated on Figure 2-3.




Figure 2-3: Holmes Block Assumed Connection Point

West Melton Plan Changes

Four proposed Plan Changes were represented in the model for this assessment having a total of 858 lots. Details of the proposed plan changes are as follows:

- Plan Change 59 – 72 lots
- Plan Change 67 - 131 lots
- Plan Change 74 - 130 lots
- Plan Change 77 - 525 lots

Flows from the West Melton plan change areas were calculated in accordance with SDC's Engineering Code of Practice. Table 2-2 below summarises the potential flows from the developed plan change areas in West Melton.

Table 2-2: Calculated Flows for West Melton Plan Change Areas

Plan Change Block	Proposed No. of Lots	Population	Calculated ADWF (L/s)	Calculated PWWF (L/s)
West Melton (PC numbers 59, 67, 74 and 77)	858	2317	5.9	29.5

Calculated design flows from West Melton were loaded directly to the Gainsborough pump station wet well. A model scenario was set up for both dry weather and peak wet weather flow conditions, corresponding to the dry and wet scenarios modelled for the Holmes Block.

3 Wastewater Servicing Options

There are two nominated connection points for the Two Chain Road Block to SDC's gravity network. The flows from the site may be split once the site develops but for the purposes of this assessment each connection point has been considered separately to take the full flow:

1. **Option 1 – Service via Jones Road:** Flows are loaded to manhole asset ID 78634 at the intersection of Railway Road and Jones Road. The flows are then conveyed through the gravity network to George Holmes Road pump station which pumps directly to the Pines WWTP in a common rising main it shares with Burnham School Road PS.
2. **Option 2 – Service via Walkers Road:** Flows are loaded to manhole asset ID 98559 at the intersection of Two Chain Road and Walkers Road. The flows are then conveyed by gravity to Burnham School Road pump station and directly to the Pines WWTP through a common rising main shared with George Holmes Road pump station.

Figure 3-1 presents the location of the connection point options described above.




Figure 3-1: Two Chain Block Connection Point Options

4 Modelling Methodology

Servicing Options 1 and 2 were modelled using the following methodology:

1. A base dry weather scenario was created in the ESSS network model. In this scenario two new subcatchments were added to represent the Holmes Block and West Melton Plan Change areas. Population was assigned to these subcatchments to allow the impact of the diurnal flow from the developments to be assessed. A third new subcatchment was added to represent flows from Iport 27 ha Extension. As this is an industrial area, the calculated design flow was applied as a constant flow.
2. A base wet weather scenario was again created in the ESSS network model. In this scenario three new subcatchments were added to represent the Holmes Block, West Melton Plan and Iport 27 ha Extension. The maximum calculated design flow was applied as a constant flow with no contributing area or population as these are accounted for in the flow applied. The flow applied for the Iport 27 ha Extension is the same in both the dry and wet weather scenarios.
3. Simulations were run to assess the impact of the Two Chain Block on the existing network during dry and wet weather.

5 Modelling Results

The predicted impact of the two connection options is presented for below.

5.1 Option 1 - Service via Jones Road

5.1.1 *Dry Weather Results*

No issues are predicted in the gravity network downstream of the connection point. George Holmes pump station is also predicted to have capacity to accommodate dry weather flows from the Two Chain Block. With the George Holmes pump station pumping increased flows from the Two Chain Block, the Burnham School Road pump station is still capable of pumping the peak inflow.

Figure 5-1 presents the model maximum hydraulic grade line (HGL) profile for Option 1 under peak dry weather flow conditions from the load point to the George Holmes PS.

5.1.2 *Wet Weather Results*

As no wet weather flow response has been observed in the George Holmes pump station, and were not included for the Two Chain Block, peak wet weather results are the same as those reported for dry weather conditions.




Figure 5-1: Long section at PDWF in the from manhole Asset ID 78634 to George Holmes PS. Predicted levels in the current system without the Two Chain Block is shown by the red line.

5.2 Option 2 - Service via Walkers Road

5.2.1 Dry Weather Results


The gravity network downstream of the Two Chain Block load point is predicted to surcharge under peak dry weather flow conditions. No manhole overflows are predicted, however the maximum water level is within 0.5 m from the ground surface at manhole Asset ID 43403 on Dunns Crossing Road. The Burnham School Road pump station is predicted to have capacity to accommodate additional peak flows.


Figure 5-2 presents the model maximum HGL profile for Option 2 under peak dry weather flow conditions from the load point to the Burnham School Road pump station.

5.2.2 Wet Weather Results

Under peak wet weather flow conditions flooding is predicted from manhole Asset ID 43403 on Dunns Crossing Road due to limited pipe capacity. To resolve flooding, an upgrade of approximately 2.2 km of pipe along Dunns Crossing Road and Burnham School Road is required. If these pipes were to be upgraded, the peak wet weather inflow to Burnham School Road pump station is 99 L/s, however the current modelled capacity is 94 L/s. This indicates that in addition to network upgrades, the capacity of the Burnham School Road pump station may need to be increased to accommodate flows from the Two Chain Block.

Figure 5-3 presents the model maximum HGL profile for Option 2 under peak wet weather flow conditions from the load point to the Burnham School Road pump station.





6 Conclusions

Servicing the Two Chain Block through manhole Asset ID 78634 on Jones Road (Option 1) is not predicted to cause any capacity issues in the downstream network under both dry and wet weather flows. The George Holmes pump station is also predicted to have sufficient capacity to cater for the additional flow from the development.

Servicing the Two Chain Block through manhole Asset ID 98559 on Walkers Road (Option 2) is predicted to result network surcharging under dry weather flow conditions and overflows during wet weather. To resolve capacity issues, network upgrades will be required along Dunns Crossing Road and Burnham School Road, as well as a potential upgrade of the Burnham School Road pump station.

7 Limitations

- This assessment has not considered whether the Pines WWTP has capacity to accept flow from the developments.
- Flows to the George Holmes pump station are based on flow records for 2019 provided by SDC.
- During validation of the model a wet weather response was identified in the Runners Road pump station catchment (upstream of Burnham School Road pump station) that has not been represented in the model. This may result in the peak wet weather inflows to the Burnham School Road pump station underrepresented by the current model.

wsp

wsp.com/nz

APPENDIX B | WSP Water Supply Network Capacity Assessment

Project Number: 3-C2333.00

Rolleston Two Chain Road Plan Change

27 July 2021

CONFIDENTIAL



Water Supply Network Capacity Assessment



Contact Details


Mark de Lange

WSP
12 Moorhouse Avenue
Christchurch 8011
+64 3 363 5400
+64 27 272 5854
mark.delange@wsp.com

Document Details:


Date: 26 July 2021
Reference: 3-C2333.00
Status: Final

Prepared by



Mark de Lange
Engineer Water

Reviewed by



Estelle Boivin
Principal Hydraulic Modeller – Water

Approved for release by



Amy Harrod
Head of Water - Christchurch



Document History and Status

Revision	Date	Author	Reviewed by	Approved by	Status
0	16/07/2021	MdL	DJ	AH	Final
1	26/07/2021	MdL	EB	AH	Final

Revision Details

Revision	Details
1	Revision as per comments form Rolleston Industrial Developments Ltd.



Contents

Disclaimers and Limitations.....	1
1 Summary	2
2 Assumptions	2
3 Water Supply Servicing Options.....	2
4 Water Supply Infrastructure Recommendations.....	3
4.1 Impact on Current Network.....	3
4.2 Servicing Options.....	6
5 Conclusions.....	7
6 Limitations.....	7

List of Figures

Figure 3-1: Demand connection points into Rolleston Water Supply network	3
Figure 4-1: Option 1 Headlosses (m/km) in Rolleston Water Supply network.....	4
Figure 4-2: Option 1 Minimum pressure (m) in Rolleston Water Supply network	4
Figure 4-3: Option 2 Headlosses (m/km) in Rolleston Water Supply network.....	5
Figure 4-4: Option 2 Minimum pressure (m) in Rolleston Water Supply network.....	6

List of Tables

Table 2-1: Water Supply Demand at the Proposed Development.....	2
---	---

Disclaimers and Limitations

This report ('**Report**') has been prepared by WSP exclusively for Rolleston Industrial Developments Ltd. ('**Client**') in relation to the Two Chain Road Plan Change in Rolleston ('**Purpose**') and in accordance with the scope of works provided via email on 6 July 2021. The findings in this Report are based on and are subject to the assumptions specified in the Report and other model modelling reports addressed to Selywn District Council. WSP accepts no liability whatsoever for any reliance on or use of this Report, in whole or in part, for any use or purpose other than the Purpose or any use or reliance on the Report by any third party.

1 Summary

WSP was engaged by Rolleston Industrial Developments Ltd. to assess the water supply network capacity and options to support the plan change of 98.3 ha of land on Two Chain Road in Rolleston to industrial.

Our assessment has identified that connection of the Two Chain Block to the Rolleston water supply network through the existing DN 300 main on Jones Road will not have any adverse effects that impede the rezoning of the land for industrial use. New sources and select pipe upgrades will be required to meet peak demand and reduce pipe headlosses. Required upgrades will include outlet pipes from the Izone water treatment plant (WTP) and approximately 425 m of pipe on IZone Drive.

SDC has additional wells and network upgrades planned as part of their ongoing water supply long-term planning. Therefore, depending on the timing of system upgrades and the timing of the uptake and construction on the proposed plan change area, sufficient water supply may be available to service Two Chain block.

2 Assumptions

The site was added to the demand in the 2020 peak day model. The demand assumptions are as follows:

- The peak design flow is 1 litre per second per hectare (1 L/s/ha) in accordance with 'NZS4404:2010 Land Development and Sub-Division' as adopted for the Izone Industrial Park and previous IPort assessments.
- Other developments that were considered in this assessment include the IPort 27 ha Extension (as is documented in memorandums addressed to Rolleston Industrial Developments Ltd. from December 2020).

Table 2-1 summarises the water supply demand at the Two Chain Road industrial area.

Table 2-1: Water Supply Demand at the Proposed Development

Area	Area (ha)	Peak Demand (L/s)
Two Chain Road	98.3	98.3

3 Water Supply Servicing Options

There are two nominated connection points to SDC's existing water supply network. Demand from the site may be split once the site develops but for the purposes of this assessment each connection point has been considered separately to take the full demand:

1. **Option 1 – Service via Jones Road:** Demand is loaded to the DN 300 main at the intersection of Jones Road and Izone Drove.
2. **Option 2 – Service via Walkers Road:** Demand loaded to the DN 150 main on Walkers Road at the west end of the site (DN 150 main is the largest pipe crossing the highway at rail lines at the west end of the Two Chain Block).

Figure 3-1 presents the location of the connection point options described above.




Figure 3-1: Demand connection points into Rolleston Water Supply network

4 Water Supply Infrastructure Recommendations

4.1 Impact on Current Network

Option 1 – Service via Jones Road

The below figures present the hydraulic performance of the existing network with demand added to the Two Chain Industrial area as per Option 1. Figure 4-1 presents maximum pipe headloss and Figure 4-2 presents minimum pressure, both under peak day demand.



Figure 4-1: Option 1 Headlosses (m/km) in Rolleston Water Supply network

As seen on Figure 4-1, headlosses in the DN 300 main on Izone Drive have increased to above 10 m/km from the outlet of the IZone Water Treatment Plant (WTP) to the development connection point. Previously, in the Iport 27 ha Block network capacity assessment, it was noted that the headlosses in main had increased beyond the desired maximum of 4 m/km



Figure 4-2: Option 1 Minimum pressure (m) in Rolleston Water Supply network

As shown in Figure 4-2, minimum pressures are below 30 m in the northern portions of the network (Detroit Drive area and connection points of the Iport 27 ha Block). The Izone demand exceeds the current well capacity, leading to the Izone Reservoir level dropping rapidly during peak demand and resulting in low pressures.

It is recommended that for this option the site be serviced by extending the existing DN 300 main on Jones Road into the Two Chain Road Block. This main will be suitable to provide the required fire flows (FW4) to the Two Chain Block, however details of this will need to be confirmed during design.

Option 2 – Service via Walkers Road

Figures 4.3 and 4.4 present maximum pipe headloss and minimum pressure respectively for Option 2 under peak day demand.



Figure 4-3: Option 2 Headlosses (m/km) in Rolleston Water Supply network




Figure 4-4: Option 2 Minimum pressure (m) in Rolleston Water Supply network

As seen on the above figures, servicing the Two Chain Block via the DN 150 at the western end of the block results in substantial headlosses, and widespread low pressure south of the highway. It is not recommended the Two Chain Block be serviced through this portion of the network at its existing size.

4.2 Servicing Options

The following recommendations were developed to improve pressure and reduce headlosses in the network:

- Upgrade the Izone WTP (with additional new sources) and outlet pipe, as well as approximately 425 m of pipes on IZone Drive; or
- Add new sources (wells) within the Izone / IPort area.

The location of the required network upgrades are shown below on Figure 4-5



Figure 4-5: Pipe Upgrades Required to Service Two Chain Block (Upgrades Shown in Red)

5 Conclusions

Additional local wells or network upgrades (treatment plant upgrade and pipe upgrades) will be required to meet the design flow determined for the Two Chain industrial area without reducing the level of service in the surrounding network. SDC has additional wells and network upgrades planned as part of their ongoing water supply long-term planning. Therefore, depending on the timing of system upgrades and the timing of the uptake and construction on the proposed plan change area, sufficient water supply may be available to service Two Chain block.

6 Limitations

This memorandum has the following limitations:

- This assessment has only considered the existing demand and demand from the developments noted.
- This assessment has not considered any local pipework within the Two Chain area. Internal pipework to service individual lots will need to be designed accordingly to accommodate peak day/ hour demand.



wsp.com/nz

APPENDIX C | Site Plans

- Site Location Plan
- Site Overview Plan including LiDAR Contours & Aerial Photograph
- Detailed Site Plans showing Lot & DP Numbers

TWO CHAIN ROAD INDUSTRIAL PARK

TWO CHAIN ROAD, ROLLESTON




LOCATION PLAN

NO.	DESCRIPTION	DATE
1	ISSUED FOR PERMIT	10/09/21
2	FOR COMMENTS	04/02/22
3	REVISED ISSUE	
4		
5		

SCALE: NOT TO SCALE
DRAWING NO. 000 REV. B
PROJECT NO: 15010

This document shall only be reproduced in full with approval from Inovo Projects Ltd.





NOTES

- 1. LIDAR data from LINZ Data Service - 1m DEM
- 2. LIDAR Major contours 2.5m interval, minor 0.5m.
- 3. Boundary information from LINZ Data Service
- 4. Services information from Selwyn District Council

A1 SCALE 1:3000 A3 SCALE 1:6000
0 50 100 150 200 250 300 (m)



Rev	Description	Drawn	Date
B	REVISED ISSUE	CPS	04.02.22
A	PRELIMINARY ISSUE	LABM	09.07.21

Level 1, 93 Manchester St, Christchurch 8022
Ph: 03 377 3290
www.inovo.nz

Project: TWO CHAIN ROAD INDUSTRIAL LTD

Client: TWO CHAIN ROAD INDUSTRIAL PARK

Scale A1: 1:3000
Scale A3: 1:6000

Designed: [blank]
Approved: [blank]
TDM: [blank]
Date: 24.08.2021

DO NOT SCALE FROM DRAWING

FILE: G:\Work\Sync\Inovo Data - Documents\1 Projects\05500001500 - Two Chain Industrial Park\05 Information Management\03 CAD\0500 - S - 01.dwg PLOTTED: 4/02/2022 10:53 PM BY: Cans

FOR INFORMATION

Drawing No: 15010-S-001

Rev: B

SITE OVERVIEW PLAN

TWO CHAIN ROAD INDUSTRIAL PARK




NOTES

- 1. Boundary information from LINZ Data Service

LEGEND

Site Boundary



A1 SCALE 1:3000 A3 SCALE 1:6000
0 50 100 150 200 250 300 (m)

Rev	Description	Drawn	Date
B	REVISED ISSUE		
A	FOR INFORMATION		

Level 1, 93 Manchester St, Christchurch 8022
Ph: 03 377 3290
Ph: 09 600 1099
www.inovo.nz

Scale A1	Scale A3
1:3000	1:6000
Designed	Approved
TDM	TDM
Date	Date

TWO CHAIN ROAD INDUSTRIAL LTD

Client

TWO CHAIN ROAD INDUSTRIAL PARK

Project

EXISTING SITE OVERVIEW PLAN

Drawing Title

FOR INFORMATION

Drawing No. **15010-E-100**

Rev **B**



NOTES

1. Boundary information from LINZ Data Service

LEGEND

Site Boundary



A1 SCALE 1:500 A3 SCALE 1:3000
10 20 30 40 50 60 70 80 90 100 150 (m)

Rev	Description	Drawn	Date
B	REVISED ISSUE		
A	FOR INFORMATION		

Level 1, 93 Manchester St, Christchurch 8022
Ph: 03 377 3290
Ph: 09 600 1099
www.inovo.nz

Scale A1	Scale A3
1:500	1:3000
Designed	Approved
24/08/2021	24/08/2021
TDM	Date

Client	Project
TWO CHAIN ROAD INDUSTRIAL LTD	TWO CHAIN ROAD INDUSTRIAL PARK

Drawing Title	Sheet
EXISTING SITE DETAILED PLAN SHEET 1	FOR INFORMATION

Drawing No.	Rev
15010-E-101	B



NOTES

1. Boundary information from LINZ Data Service

LEGEND

Site Boundary



AI SCALE 1:500 A3 SCALE 1:3000
10m 0 10 20 30 40 50 60 70 80 90 100 150 (m)

Rev#1 Description Drawn Date

B1 REVISIONS

A1 FOR INFORMATION

FILE & Work Sync/Draw Project/Info Data - Documents\1 Projects\055000\5000 - Two Chain Industrial Park\05 Information Management\03 Engineering\02 CAD\5000-5000.dwg PLOTTED: 4/02/2022 10:58 PM BY: Chris



Level 1, 93 Manchester St, Christchurch 8022
Ph: 03 377 3290
Ph: 09 600 1099
www.inovo.nz

Scale AI
1:500
Scale A3
1:3000
DO NOT SCALE FROM DRAWING

Designed
Approved
TDM
Date

Client
TWO CHAIN ROAD INDUSTRIAL LTD

Project
TWO CHAIN ROAD INDUSTRIAL PARK

Drawing Title
EXISTING SITE DETAILED PLAN SHEET 2

Stage
FOR INFORMATION
Drawing No.
15010-E-102
Rev
B



NOTES

1. Boundary information from LINZ Data Service

LEGEND

Site Boundary



Rev

Description

Drawn

Date

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362

363

364

365

366

367

368

369

370

371

372

373

374

375

376

377

378

379

380

381

382

383

384

385

386

387

388

389

390

391

392

393

394

395

396

397

398

399

400

401

402

403

404

405

406

407

408

409

410

411

412

413

414

415

416

417

418

419

420

421

422

423

424

425

426

427

428

429

430

431

432

433

434

435

436

437

438

439

440

441

442

443

444

445

446

447

448

449

450

451

452

453

454

455

456

457

458

459

460

461

462

463

464

465

466

467

468

469

470

471

472

473

474

475

476

477

478

479

480

481

482

483

484

485

486

487

488

489

490

491

492

493

494

495

496

497

498

499

500

501

502

503

504

505

506

507

508

509

510

511

512

513

514

515

516

517

518

519

520

521

522

523

524

525

526

527

528

529

530

531

532

533

534

535

536

537

538

539

540

541

542

543

544

545

546

547

548

549

550

551

552

553

554

555

556

557

558

559

560

561

562

563

564

565

566

567

568

569

570

571

572

573

574

575

576

577

578

579

580

581

582

583

584

585

586

587

588

589

590

591

592

593

594

595

596

597

598

599

600

601

602

603

604

605

606

607

608

609

610

611

612

613

614

615

616

617

618

619

620

621

622

623

624

625

626

627

628

629

630

631

632

633

634

635

636

637

638

639

640

641

642

643

644

645

646

647

648

649

650

651

652

653

654

655

656

657

658

659

660

661

662

663

664

665

666

667

668

669

670

671

672

673

674

675

676

677

678

679

680

681

682

683

684

685

686

687

688

689

690

691

692

693

694

695

696

697

698

699

700

701

702

703

704

705

706

707

708

709

710

711

712

713

714

715

716

717

718

719

720

721

722

723

724

725

726

727

728

729

730

731

732

733

734

735

736

737

738

739

740

741

742

743

744

745

746

747

748

749

750

751

752

753

754

755

756

757

758

759

760

761

762

763

764

765

766

767

768

769

770

771

772

773

774

775

776

777

778

779

780

781

782

783

784

785

786

787

788

789

790

791

792

793

794

795

796

797

798

799

800

801

802

803

804

805

806

807

808

809

810

811

812

813

814

815

816

817

818

819

820

821

822

823

824

825

826

827

828

829

830

831

832

833

834

835

836

837

838

839

840

841

842

843

844

845

846

847

848

849

850

851

852

853

854

855

856

857

858

859

860

861

862

863

864

865

866

867

868

869

870

871

872

873

874

875

876

877

878

879

880

881

882

883

884

885

886

887

888

889

890

891

892

893

894

895

896

897

898

899

900

901

902

903

904

905

906

907

908

909

910

911

912

913

914

915

916

917

918

919

920

921

922

923

924

925

926

927

928

929

930

931

932

933

934

935

936

937

938

939

940

941

942

943

944

945

946

947

948

949

950

951

952

953

954

955

956

957

958

959

960

961

962

963

964

965

966

967

968

969

970

971

972

973

974

975

976

977

978

979

980

981

982

983

984

985

986

987

988

989

990

991

992

993

994

995

996

997

998

999

1000

1001

1002

1003

1004

1005

1006

1007

1008

1009

1010

1011

1012

1013

1014

1015

1016

1017

1018

1019

1020

1021

1022

1023

1024

1025

1026

1027

1028

1029

1030

1031

1032

1033

1034

1035

1036

1037

1038

1039

1040

1041

1042

1043

1044

1045

1046

1047

1048

1049

1050

1051

1052

1053

1054

1055

1056

1057

1058

1059

1060

1061

1062

1063

1064

1065

1066

1067

1068

1069

1070

1071

1072

1073

1074

1075

1076

1077

1078

1079

1080

1081

1082

1083

1084

1085

1086

1087

1088

1089

1090

1091

1092

1093

1094

1095

1096

1097

1098

1099

1100

1101

1102

1103

1104

1105

1106

1107

1108

1109

1110

1111

1112

1113

1114

1115

1116

1117

1118

1119

1120

1121

1122

1123

1124

1125

1126

1127

1128

1129

1130

1131

1132

1133

1134

1135

1136

1137

1138

1139

1140

1141

1142

1143

1144

1145

1146

1147

1148

1149

1150

1151

1152

1153

1154

1155

1156

1157

1158

1159

1160

1161

1162

1163

1164

1165

1166

1167

1168

1169

1170

1171

1172

1173

1174

1175

1176

1177

1178

1179

1180

1181

1182

1183

1184

1185

1186

1187

1188

1189

1190

1191

1192

1193

1194

1195

1196

1197

1198

1199

1200

1201

1202

1203

1204

1205

1206

1207

1208

1209

1210

1211

1212

1213

1214

1215

1216

1217

1218

1219

1220

1221

1222

1223

1224

1225

1226

1227

1228

1229

1230

1231

1232

1233

1234

1235

1236

1237

1238

1239

1240

1241

1242

1243

1244

1245

1246

1247

1248

1249

1250

1251

1252

1253

1254

1255

1256

1257

1258

1259

1260

1261

1262

1263

1264

1265

1266

1267

1268

1269

1270

1271

1272

1273

1274

1275

1276

1277

1278

1279

1280

1281

1282

1283

1284

1285

1286

1287

1288

1289

1290

1291

1292

1293

1294

1295

1296

1297

1298

1299

1300

1301

1302

1303

1304

1305

1306

1307

1308

1309

1310

1311

1312

1313

1314

1315

1316

1317

1318

1319

1320

1321

1322

1323

1324

1325

1326

1327

1328

1329

1330

1331

1332

1333

1334

1335

1336

1337

1338

1339

1340

1341

1342

1343

1344

1345

1346

1347

1348

1349

1350

1351

1352

1353

1354

1355

1356

1357

1358

1359

1360

1361

1362

1363

1364

1365

1366

1367

1368

1369

1370

1371

1372

1373

1374

1375

1376

1377

1378

1379

1380

1381

1382

1383

1384

1385

1386

1387

1388

1389

1390

1391

1392

1393

1394

1395

1396

1397

1398

1399

1400

1401

1402

1403

1404

1405

1406

1407

1408

1409

1410

1411

1412

1413

1414

1415

1416

1417

1418

1419

1420

1421

1422

1423

1424

1425

1426

1427

1428

1429

1430

1431

1432

1433

1434

1435

1436

1437

1438

1439

1440

1441

1442

1443

1444

1445

1446

1447

1448

1449

1450

1451

1452