# **Approved Building Consent Documents**

Please Note: A copy of the stamped approved documents must be available on site for all inspections.

#### **Inspection booking timeframes**

Call received	before 3pm inspection	after 3pm inspection
	will be done	will be done
Monday	Wednesday	Thursday
Tuesday	Thursday	Friday
Wednesday	Friday	Monday
Thursday	Monday	Tuesday
Friday	Tuesday	Wednesday

Building inspections and enquiries phone: 03 347 2839

Please ensure all work for inspection is ready the day before. Incomplete work requiring re-inspection will incur an additional inspection fee.

Reference Number: 180748.1 Project Location: 116 mcDonald Road Lincoln Project Pescription: Farm Building McDonald Rd McDonald Rd McDonald Rd Resource Consent # RC195342

has been granted on 03/07/19

bigsbr 3/07/2019



#### **GENERAL**

G1. READ THESE DRAWINGS IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER WORKING DRAWINGS, SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT G2. PROVIDE ALL WORKMANSHIP AND MATERIALS IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT EDITIONS OF THE NZ BUILDING ACT. THE NZ BUILDING CODE, THE NEW ZEALAND STANDARDS AND THE BY-LAWS AND ORDINANCES OF THE RELEVANT BUILDING CONSENT AUTHORITY. G3. COMPLY AS THE BUILDER, WITH REQUIREMENTS OF THE WORKPLACE **HEALTH & SAFETY ACT** 

G4. REFER ANY CONFLICT BETWEEN THESE NOTES, THE SPECIFICATION, THE DRAWINGS OR ANY OTHER RELEVANT DOCUMENTS TO THE ENGINEER FOR

DECISION PRIOR TO PROCEEDING WITH THE WORK G5. DO NOT OBTAIN DIMENSIONS BY SCALING THE DRAWINGS. FOR SETTING OUT

DIMENSIONS AND LEVELS REFER TO ARCHITECTURAL DRAWINGS.

G6. THE BUILDER IS RESPONSIBLE FOR THE PROVISION OF ALL SHORING TO MAINTAIN THE STABILITY AND INTEGRITY OF EXCAVATIONS AND ADJACENT STRUCTURES. PROVIDE DETAILS, FOR REVIEW BY THE ENGINEER, OF ANY NECESSARY TEMPORARY WORKS, INCLUDING SHORING,

PRIOR TO COMMENCING CONSTRUCTION.

DURING CONSTRUCTION IT IS THE BUILDER'S RESPONSIBILITY TO MAINTAIN THE STRUCTURE IN A STABLE CONDITION AND TO ENSURE NO PART IS OVERSTRESSED.

G8. THE DESIGN AND DRAWINGS ARE COPYRIGHT AND MAY NOT BE USED OR REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF THE

FIRE-RESISTANT LEVELS (FRL'S) REQUIRED FOR THE VARIOUS STRUCTURAL ELEMENTS MUST BE CONFIRMED BY THE BUILDING SURVEYOR OR ARCHITECT.

#### **FOUNDATIONS**

F1. THE MINIMUM SAFE BEARING CAPACITY OF FOUNDATION MATERIAL SHALL BE: SLABS & FOOTINGS: 300 kPa.(ULS) U.N.O.

F2. FOUNDATION MATERIAL SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACING CONCRETE

F3. THE BASES OF FOOTING EXCAVATIONS SHALL BE FINISHED CLEAN AND HORIZONTAL AND BE EMBEDDED 300 INTO BEARING GROUND OR AS NOTED ON **DETAILS** 

F4. FOUNDING LEVELS WHERE SHOWN ARE FOR TENDER PURPOSES ONLY.

F5. ANY PROPOSED FOOTING EXCAVATION NEAR BOUNDARIES, OTHER STRUCTURES OR SERVICES SHALL BE APPROVED BY THE ENGINEER.

F6. SUBGRADE SHALL BE APPROVED MATERIAL COMPACTED TO 98% STANDARD DRY DENSITY DETERMINED BY TESTING TO THE RELEVANT PART OF NZS 4402: 1986 U.N.O F7. LOCATE ALL NEW FOOTINGS RELATIVE TO LINE OF CUT/EXCAVATION INCLUDING **EXCAVATIONS AS FOLLOWS:** 

LINE OF INFLUENCE

LINE OF CUT OF **EXCAVATION FOR** RETAINING WALL 1 MAX FOUND ALL FOUNDATIONS BELOW LINE OF INFLUENCE OF **EXISTING CUT OR EXISTING FOOTINGS UNLESS NOTED** 

2 FOR SAND 1 FOR CLAY 0 FOR ROCK

\*SUBJECT TO APPROVAL FROM THE GEOTECHNICAL ENGINEER

#### **LOADINGS**

L1. SUPERIMPOSED FLOOR LOADS ARE IN ACCORDANCE WITH AS/NZS1170.1: DOMESTIC FLOORS : 1.5 kPA BALCONIES : 2.0kPa

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting

Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of

DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content

contained on this drawing. The Contractor must verify all dimensions on site before commencing

any work or making any shop drawings. Figured dimensionsmust be taken in preference to scaled

STAIRS: 2.0kPa

dimensions. All scaled dimensions must be verified on site.

PRINTED 20/08/2019 7:32:52 AM

L2. WIND LOADS ARE IN ACCORDANCE WITH AS/NZS1170.2 FOR: TERRAIN CATEGORY: 2.5 **REGION A7** SHIELDING MULTIPLIER OF 1.0 **TOPOGHRAPHIOC MULTIPLIER OF 1.0** 

L3. SNOW LOADS ARE IN ACCORDANCE WITH AS./NZS1170.3

L4. EARTHQUAKE LOADS ARE IN ACCORDANCE WITH NZS1170.5 FIGURED DIMENSIONS TAKE PRECEDENCE.

#### REINFORCED CONCRETE

PROVIDE ALL WORKMANSHIP AND MATERIALS IN ACCORDANCE WITH NZS 3101.1:2006, AND NZS 3109:1997, THEIR REFERENCED DOCUMENTS, THE DRAWINGS AND THE SPECIFICATION.

PROVIDE CONCRETE COMPOSITION AND MINIMUM CLEAR CONCRETE COVER TO **REINFORCEMENT AS FOLLOWS:-**

**ELEMENT** NZS 3604 COVER F'c MPa

**SLABS & FOOTINGS** 20 75 BTM & SIDES (WHERE NO D.P.M) 50 BTM & SIDES (WHERE D.P.M) **35 TOP** 

C3. SUPPORT ALL REINFORCEMENT AT 1 METRE MAXIMUM CENTRES BOTH WAYS ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS. USE ONLY PLASTIC CHAIRS FOR EXTERNALLY EXPOSED SOFFITS

PROVIDE ALL CONCRETE WITH 80mm MAXIMUM SLUMP, 20mm MAXIMUM AGGREGATE WITH NO ADMIXTURES, UNLESS APPROVED BY THE ENGINEER

SIZES OF CONCRETE ARE NET, EXCLUSIVE OF APPLIED FINISHES. BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE SLAB THICKNESS.

PROPERLY FORM CONSTRUCTION JOINTS AND USE ONLY WHERE SHOWN ORAPPROVED BY THE ENGINEER.

C7. DELETED

REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY AND IS NOTNECESSARILY SHOWN IN TRUE PROJECTION.

C9. WELD OR SPLICE REINFORCEMENT ONLY IN POSITIONS APPROVED BY THE

C10. PROVIDE THE MINIMUM CLEAR SPACING BETWEEN CONDUITS, CABLES, PIPES AND BARS AS REQUIRED BY NZS 3109 BUT NOT LESS THAN THREE BARDIAMETERS. DO NOT PLACE CONDUITS IN SLABS ABOVE TOP REINFORCEMENT OR BELOW BOTTOM REINFORCEMENT. C11.

D - DENOTES HOT ROLLED DEFORMED BARS GRADE 300E HD - DENOTES HOT ROLLED DEFORMED BARS GRADE 500E.

R - DENOTES HOT ROLLED PLAIN ROUND BARS GRADE 230R

SE, RE - DENOTES HARD DRAWN WIRE FABRIC GRADE 500E.

C12. NOTIFY THE ENGINEER A MINIMUM OF 24 HOURS BEFORE REINFORCEMENT HAS BEEN COMPLETED. ALLOW 2 HOURS AFTER THE COMPLETION OF THE REINFORCEMENT FOR THE ENGINEER'S INSPECTION. DO NOT ORDER REINFORCEMENT FOR THE ENGINEER'S INSPECTION. DO NOT ORDER CONCRETE UNTIL REINFORCEMENT HAS BEEN APPROVED BY THE ENGINEER.

C13. CURE CONCRETE IN ACCORDANCE WITH NZS 3109. COMMENCE CURING WITHIN TWO HOURS OF FINISHING OPERATIONS AND CONTINUE FOR A MINIMUM OF SEVEN DAYS BY USING AN APPROVED PROPRIETARY COMPOUNDOR BY KEEPING CONTINUOUSLY WET. C14. TIE ALL UNSUPPORTED BARS IN TRANSVERSE DIRECTION TO D12-300, LAPPED 500

C15. LAP FABRIC IN ACCORDANCE WITH CLAUSE 8.7.6 OF NZS 3109

C16 PROVIDE HOOKS, LAPS AND BENDS IN ACCORDANCE WITH NZS 3101 & NZS 3109 U.N.O.

PROVIDE CHAMFERS, DRIP GROOVES ETC. IN ACCORDANCE WITH THE ARCHITECT'S DETAILS.

DESIGN, CONSTRUCT AND STRIP FORMWORK IN ACCORDANCE WITH NZS 3109. PRE CAMBER FORMWORK UPWARDS BY 1/500 OF THE CLEAR SPAN U.N.O.WHERE

SUPPORTED BEAMS AND SLABS SPAN GREATER THAN 5m. THE CONCRETE ELEMENTS DETAILED HAVE AN F.R.L. OF 60/60/60 U.N.O.

**APPROVED** 

T1. ENSURE ALL WORKMANSHIP AND MATERIALS ARE IN ACCORDANCE WITH NZS 3603:1993 AND NZS 3604:2011, THEIR REFERENCED DOCUMENTS AND THE SPECIFICATION

T2. PROVIDE ALL INTERIOR TIMBER AS SG6 (DRY) U.N.O. PROVIDE ALL EXTERNAL TIMBER ASSG8 (DRY) U.N.O.

T3. WHERE THE USE OF TREATED TIMBER FOR DURABILITY IS NOTED ON THE STRUCTURAL DRAWINGS, ENSURE IT COMPLIES WITH THE PARAMETERS: EXPOSURE ZONE C IN ACCORDANCE WITH NZS 3604

T4. INSTALL PROPRIETARY TIMBER CONNECTORS IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.

T5. RETIGHTEN BOLTED CONNECTIONS IN UNSEASONED TIMBER PRIOR TO THE FIXING OF CLADDING T6. TIMBER ELEMENTS OR TIMBER FRAMING HAVE NOT BEEN DESIGNED UNLESS

NOTED T7. ALL TRUSSES TO BE PRE-CAMBERED UPWARD 1/240 SPAN U.N.O

Structural Specification

Project Status B Jessep 133 Greenpark Road DMG DESIGNED DRAWN CAD Christchurch CHECKED PDD Container Shed

DUNCAN MANAGEMENT GROUP | 96 Kerrs Rd SKIPSTONE CONSULTING | Christchurch

project managers | p (+64) 021 397008

consulting engineers | e. peterd@skipstoneconsulting.co.nz

А3 ORIGINAL SCALE 1:149 PROJECT NO 190514 200 SHEET Offices in Australia and New Zealand

Issue Date

DATE

**MASONRY** 

Revision

Number

M1. ENSURE ALL WORKMANSHIP AND MATERIALS ARE IN ACCORDANCE WITH NZS 4230, THE DRAWINGS & STANDARD TECHNICAL SPECIFICATIONS.

**Revision Schedule** 

**Revision Description** 

Revision

WHERE MASONRY SUPPORTS CONCRETE SLABS OR BEAMS, LAY THE TOP COURSE WITH FROGS DOWN AND COVERED WITH 2 LAYERS OF APPROVEDSLIP JOINT MATERIAL. WALLS SHOWN SHADED ON PLAN ARE LOAD BEARING.

SEPARATE NON-LOAD BEARING WALLS UNDER SLABS FROM THE SLAB BY 15mm OF APPROVED COMPRESSIBLE MATERIAL.

WHERE MASONRY ABUTS SLAB DOWNTURNS, 15mm GAP BETWEEN BRICKWORK AND SIDE OF DOWNTURN.

DO NOT ERECT MASONRY SUPPORTED BY CONCRETE SLABS OR BEAMS UNTIL ALL FORMWORK AND PROPS UNDER HAVE BEEN REMOVED.

PROVIDE ALL BRICKS OF STRENGTH F'UC= 20 MPa U.N.O.

M6. PROVIDE ALL HOLLOW CONCRETE MASONRY OF STRENGTH F'UC = 15 MPa U.N.O.

PROVIDE CLASSIFICATION M3 MASONRY MORTAR U.N.O. NOTE THAT WITHIN100m FROM NON-SURF COAST, OR 1KM FROM SURF COAST, PROVIDE CLASSIFICATION M4 MASONRY MORTAR

CUT NO CHASES INTO LOADBEARING MASONRY WITHOUT THE APPROVAL OF THE

PROVIDE MOVEMENT CONTROL JOINTS VERTICALLY FOR FULL HEIGHT OFWALL AS М9 FOLLOWS:

FOR GENERAL MASONRY, AT 8m MAXIMUM CENTRES & 4m MAXIMUM FROM CORNERS FOR ARTICULATED MASONRY, AT 6m MAXIMUM CENTRES & 4m MAXIMUM FROM CORNERS. PROVIDE 15mm MINIMUM JOINTS WITH AN APPROVED COMPRESSIBLEFILLER, TIED

TOGETHER EVERY 4TH COURSE WITH AN MET 3.3 MASONRY SLIDING TIE OR APPROVED

M10. CONSTRUCT HOLLOW WALLS TO FULL HEIGHT OR MAXIMUM 3m BEFORE FILLING CORES

PROVIDE CLEANOUT OPENINGS AT THE BASE OF ALL CORES TO BE FILLED

M11. PROVIDE HOLLOW F'C 20 MPa CORE FILLING CONCRETE WITH 10mm AGGREGATE. 180 SLUMP U N O

CONSTRUCT HOLLOW MASONRY RETAINING WALLS USING "DOUBLE U BLOCKS"

UNREINFORCED MASONRY WALLS HAVE NOT BEEN DESIGNED UNLESS NOTED

REINFORCED MASONRY WALLS HAVE AN F.R.L. OF -/-/- U.N.O. M14.

#### **STEELWORK**

S1. ENSURE MATERIALS, FABRICATION AND ERECTION ARE IN ACCORDANCEWITH NZS 3404, ITS REFERENCED DOCUMENTS AND THE SPECIFICATION.

S2. SUBMIT THREE COPIES OF ALL WORKSHOP DRAWINGS TO THE ARCHITECTAND THE ENGINEER TO OBTAIN THEIR WRITTEN APPROVAL PRIOR TO FABRICATION.

S3. PROVIDE ALL WELDS AS 6mm CONTINUOUS FILLET FROM E41XX ELECTRODES, ALL BOLTS AS M16-4.6/S AND ALL CLEATS AND GUSSETS AS10mm PLATE U.N.O.

S4. FOR BOLTS, THE FOLLOWING NOTATION IS USED:

4M16-4.6/S DENOTES 4 X M16 COMMERCIAL GRADE BOLTS SNUG TIGHT. 6M20-8.8/TF DENOTES 6 X M20 HIGH STRENGTH STRUCTURAL BOLTS FULLY TENSIONED

IN A NO SLIP JOINT 8M24-8.8/TB DENOTES 8 X M24 HIGH STRENGTH STRUCTURAL BOLTS FULLY TENSIONED IN A BEARING JOINT.

S5. LEAVE MATING SURFACES OF TF CONNECTIONS UNPAINTED AND FREE OF MILL

S6. TIGHTEN BOLTS IN TF AND TB CONNECTIONS USING THE PART TURNMETHOD OR LOAD INDICATING WASHERS. DO NOT USE CALIBRATED TORQUE WRENCHES. USE A HARDENED WASHER UNDER THE BOLT HEAD OR NUT, WHICHEVER IS ROTATED. THE RE-USE OF FULLY TENSIONED BOLTS IS PROHIBITED.

PROVIDE ALL CLEATS AND DRILL ALL HOLES NECESSARY FOR FIXING STEELTO STEEL OR TIMBER.

FABRICATE STEEL BEAMS AND TRUSSES SPANNING GREATER THAN 5m WITHAN UPWARD PRE CAMBER OF 1/500 SPAN U.N.O.

PREPARE STRUCTURAL STEELWORK TO CLASS 2 AND PAINT WITH ZINC PHOSPHATE PRIMER TO A THICKNESS OF 70 MICROMETRES U.N.O.


HOT DIP GALVANISE ALL EXPOSED EXTERNAL STEELWORK AND ALLSTEELWORK BUILT INTO AN EXTERNAL MASONRY SKIN, IN ACCORDANCEWITH GRADE HDG600 TO AS/NZS 2312.

WITHIN 100m FROM THE NON-SURF COAST OR 1 KM FROM THE SURF COAST, HOT DIP

GALVANISE ABOVE IN ACCORDANCE WITH GRADE HDG900 TO AS/NZS 2312. S11. PROVIDE FIRE PROTECTION TO ALL STEELWORK AS REQUIRED.

ENSURE ALL COLD FORMED SECTIONS CONFORM TO AS/NZS 4600 AND ARE ROLL-FORMED FROM STEEL STRIP, MINIMUM YIELD STRESS 450 MPa,300 g/m2 MINIMUM ZINC COATING MASS U.N.O.

	Revision Schedule	
Revision Number	Revision Description	Revision Date



## 1:100

#### **FOOTING PLAN**

#### FIGURED DIMENSIONS TAKE PRECEDENCE.

PRINTED 20/08/2019 7:32:53 AM

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content contained on this drawing. The Contractor must verify all dimensions on site before commencing any work or making any shop drawings. Figured dimensionsmust be taken in preference to scaled dimensions. All scaled dimensions must be verified on site.

Project Status DMG DESIGNED DRAWN CAD CHECKED PDD Footing Plan APPROVED PDD


B Jessep 133 Greenpark Road RD4 Christchurch Container Shed

DUNCAN MANAGEMENT GROUP | 96 Kerrs Rd SKIPSTONE CONSULTING | Christchurch project managers | p (+64) 021 397008

consulting engineers | e. peterd@skipstoneconsulting.co.nz Offices in Australia and New Zealand

ORIGINAL A3 SCALE 1:100 PROJECT NO 190514 201 SHEET DATE Issue Date


	Revision Schedule	
Revision Number	Revision Description	Revision Date



#### FIGURED DIMENSIONS TAKE PRECEDENCE.

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of	Project Statu	IS	B Jessep	DUNCAN MANAGEMENT GROUP		ORIGINAL	A3
DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content	DESIGNED	DMG	133 Greenpark Road	SKIPSTONE CONSULTING		SCALE	1:100
contained on this drawing. The Contractor must verify all dimensions on site before commencing any work or making any shop drawings. Figured dimensionsmust be taken in preference to scaled	DRAWN CAD	RD4 Christchurch	consulting engineers   e. project managers   P (	e. peterd@skipstoneconsulting.co.nz p (+64) 021 397008	PROJECT N	0190514	
dimensions.All scaled dimensions must be verified on site.	CHECKED	PDD	Container Shed		Offices in Australia and New Zealand	SHEET	202
PRINTED 20/08/2019 7:32:53 AM	APPROVED	PDD	Floor Plan		Offices in Australia and New Zealand	DATE	Issue Date

	Revision Schedule	
Revision Number	Revision Description	Revision Date




Roof Plan


1:100

#### FIGURED DIMENSIONS TAKE PRECEDENCE.

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content contained on this drawing. The Contractor must verify all dimensions on site before commencing any work or making any shop drawings. Figured dimensionsmust be taken in preference to scaled		ıs	B Jessep	DUNCAN MANAGEMENT GROUP		ORIGINAL	A3
		DMG	133 Greenpark Road RD4 Christchurch	SKIPSTONE CONSULTING consulting engineers project managers	e. peterd@skipstoneconsulting.co.nz	SCALE	1:100
		CAD				PROJECT N	0190514
dimensions.All scaled dimensions must be verified on site.	CHECKED	PDD	Container Shed		Offices in Australia and New Zealand	SHEET	203
PRINTED 20/08/2019 7:32:53 AM	APPROVED	PDD	Roof Plan		Offices in Australia and New Zealand	DATE	Issue Date



**Revision Schedule** Revision Date Revision Number **Revision Description** 



North 1:100


# Pole Plate 2-M12 Bolts mid span between Rafters Level 2 2875 Rafter on Joist hanger attached to pole plate


## Section 2 - Callout 1 1:10


#### FIGURED DIMENSIONS TAKE PRECEDENCE.

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of	Project Status	B Jessep	DUNCAN MANAGEMENT GROUP	96 Kerrs Rd	ORIGINAL A3
DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content	DESIGNED DMG	133 Greenpark Road RD4	SKIPSTONE CONSULTING	Christchurch e. peterd@skipstoneconsulting.co.nz	SCALE As indicated
contained on this drawing. The Contractor must verify all dimensions on site before commencing any work or making any shop drawings. Figured dimensionsmust be taken in preference to scaled	DRAWN CAD	Christchurch	project managers		PROJECT NO 190514
dimensions.All scaled dimensions must be verified on site.	CHECKED PDD	Container Shed		Offices in Australia and New Zealand	SHEET 205
PRINTED 20/08/2019 7:32:53 AM	APPROVED PDD	Elevations		omees in reasonable and New Zediding	DATE Issue Date

	Revision Schedule	
Revision Number	Revision Description	Revision Date







Section 3

1:20

## 1

#### corner detail Tie Down

1:10

#### FIGURED DIMENSIONS TAKE PRECEDENCE.

This drawing was produced for & remains the property of Skipstone Consulting Ltd Consulting DUNCAN MANAGEMENT GROUP | 96 Kerrs Rd Project Status B Jessep ORIGINAL A3 Engineers, (DMG). This drawing shall not be used in any manner without the prior agreement of SKIPSTONE CONSULTING | Christchurch 133 Greenpark Road DMG DMG. DMGdoes not accept any responsibility or liability to any third party as a result of the content As indicated DESIGNED consulting engineers e. peterd@skipstoneconsulting.co.nz contained on this drawing. The Contractor must verify all dimensions on site before commencing RD4 DRAWN PROJECT NO 190514 CAD any work or making any shop drawings. Figured  $\,$  dimensionsmust be taken in preference to scaled project managers | p (+64) 021 397008 Christchurch dimensions. All scaled dimensions must be verified on site. 206 **Container Shed** CHECKED PDD SHEET Offices in Australia and New Zealand Details PRINTED 20/08/2019 7:32:53 AM APPROVED PDD DATE Issue Date

#### SKIPSTONE CONSULTING

#### Peter D Duncan CPEng

Consulting Engineers & Project Managers

21 May 2019 Ref: 190514

Bruce Jessep 133 Greenpark Road RD4 Christchurch

#### RE: 133 Greenpark Road RD4 Christchurch - Container Shed and Rood

Skipstone Consulting have been engaged by Bruce Jessep of to provide structural details and tie down for containers and roofs on his property

We understand that a "show cause" notice has been issued

I have reviewed the structure and the associated foundation requirements to meet the building code.

The containers can be tied down with clamps which meet the load requirement for the structure and allow for earthquake loading of a minor building structure for storage on site.

Please find attached the related drawings and PS1 for the structural elements described. I can also provide a PS4

Kind Regards

Peter D Dunca

Peter D Duncan CPEng 144221

021 397 008







Building Code Clause(s). B1/VM1/VM4

#### PRODUCER STATEMENT – PS1 – DESIGN

(Guidance on use of Producer Statements (formerly page 2) is available at www.engineeringnz.org)

	ISSUED BY: Skipstone Consulting Ltd
camerj	(Design Firm)
Ĕ	TO: Bruce Jessep
ဗ	(Owner/Developer)
1	TO BE SUPPLIED TO: Selwyn District Council
တ	(Building Consent Authority)
/201	IN RESPECT OF: Container Shed Foundation and Design Check (Description of Building Work)
/08	AT: 116 McDonald Road
ŏ	(Address)
- 2	Town/City: Christchurch LOT DP SO (Address)
7	We have been engaged by the owner/developer referred to above to provide:
₽	Review of Structure and Foundation tie down
_	Review of Structure and Foundation tie down
g 2	
<u>a</u>	(Extent of Engagement)
1	services in respect of the requirements of Clause(s).B1
임	
$\exists$	☐ All or ■ Part only (as specified in the attachment to this statement), of the proposed building work.
;191100	The design carried out by us has been prepared in accordance with:
BC	■ Compliance Documents issued by the Ministry of Business, Innovation & Employment. VM1/VM4or
7	(verification method/acceptable solution)
⊭│	Alternative solution as per the attached schedule
ocument	
늘	The proposed building work covered by this producer statement is described on the drawings titled:
힍	Container Shed 1905 and numbered 200-206 ;
	together with the specification, and other documents set out in the schedule attached to this statement.
onsent	On behalf of the Design Firm, and subject to:
Se	(i) Site verification of the following design assumptions
	(ii) All proprietary products meeting their performance specification requirements;
ပ	I believe on reasonable grounds that a) the building, if constructed in accordance with the drawings, specifications, and other
Building	documents provided or listed in the attached schedule, will comply with the relevant provisions of the Building Code and that b),
0	the persons who have undertaken the design have the necessary competency to do so. I also recommend the following level of
$\frac{1}{2}$	construction monitoring/observation:
	CM1 CM2 ■CM3 CM4 CM5 (Engineering Categories) or as per agreement with owner/developer (Architectural)
Approved	Peter David Duncan
ă	<sub>I,</sub> Peter David Duncan am: ■ CPEng 144221 # ☐ Reg Arch#  (Name of Design Professional)
₽	I am a member of: ■ Engineering New Zealand  NZIA and hold the following qualifications:
i.	The Design Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000*.
ပ	The Design Firm is a member of ACENZ:
SD	SIGNED BY Peter David Duncan  (Signature). Read Sunces Digitally signed by Peter D Duncan Date: 2019.05.22 08:44:04 +12:00*
,	(Signature).
	· · · · · · · · · · · · · · · · · · ·
	ON BEHALF OF Skipstone Consulting Ltd Date 22-5-2019
	(Design Firm)

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000\*.

This form is to accompany Form 2 of the Building (Forms) Regulations 2004 for the application of a Building Consent.

THIS FORM AND ITS CONDITIONS ARE COPYRIGHT TO ACENZ, ENGINEERING NEW ZEALAND AND NZIA

PRODUCER STATEMENT PS1